

Draft

BALLONA WETLANDS RESTORATION PROJECT

Preliminary Design Report

Prepared for
California State Coastal Conservancy

May 8, 2013



Draft

BALLONA WETLANDS RESTORATION PROJECT

Preliminary Design Report

Prepared for
California State Coastal Conservancy

May 8, 2013



550 Kearny Street
Suite 900
San Francisco, CA 94108
415.896.5900
www.esassoc.com

Los Angeles

Oakland

Orlando

Palm Springs

Petaluma

Portland

Sacramento

San Diego

Santa Cruz

Seattle

Tampa

Woodland Hills

D120367.00

OUR COMMITMENT TO SUSTAINABILITY | ESA helps a variety of public and private sector clients plan and prepare for climate change and emerging regulations that limit GHG emissions. ESA is a registered assessor with the California Climate Action Registry, a Climate Leader, and founding reporter for the Climate Registry. ESA is also a corporate member of the U.S. Green Building Council and the Business Council on Climate Change (BC3). Internally, ESA has adopted a Sustainability Vision and Policy Statement and a plan to reduce waste and energy within our operations. This document was produced using recycled paper.



626 Wilshire Boulevard
Suite 1100
Los Angeles, CA 90017
213.599.4300 phone
213.599.4301 fax

www.esassoc.com

May 8, 2013

Mr. Richard Leifield
Chief of Engineering and Levee Safety Officer
U.S. Army Corps of Engineers, Los Angeles District
P.O. Box 532711
Los Angeles, CA 90053-2325

Subject: Ballona Wetlands Restoration Project Preliminary Design Report

Dear : Mr. Leifield

Please find enclosed the Ballona Wetlands Restoration Preliminary Design Report (PDR) as part of the Section 408 Initial Submittal A to the U.S. Army Corps of Engineers for the Ballona Wetlands Restoration Project.

This PDR documents the preliminary restoration engineering design including preliminary plans for the proposed new perimeter levees, Ballona Creek realignment, habitat restoration, and grading; anticipated O&M requirements; and preliminary geotechnical and structural engineering analyses.

The following analyses will be completed subsequent to Submittal A for CEQA/NEPA review and detailed analysis and design for Submittal B:

- This PDR includes a Preliminary Geotechnical Design Summary. A Geotechnical Report including analysis of recently collected geotechnical data is being prepared.
- This PDR includes a preliminary discussion of sediment chemical quality. A sediment quality memorandum including analysis of recently collected sediment quality data is being prepared.
- The design for managed wetland restoration behind the proposed new Culver levee, including new water control structures, is being further developed.

These additional geotechnical, sediment quality, and managed wetland design analyses will be submitted as addenda to the PDR during Summer/Fall 2013.

This PDR also refers to a draft Restoration and Adaptive Management Plan that describes the revegetation approach. The preliminary revegetation design will be developed during Summer/Fall 2013.



Mr. Richard Leifield
May 8, 2013
Page 2

The Ballona Wetlands Restoration Project Preliminary Hydrology and Hydraulics Report (H&H Report) (ESA PWA 2013) documents preliminary H&H technical analyses for the Project. Please note that the H&H Report assesses a prior iteration of the Project design and that this PDR presents the current restoration design. Since the completion of analyses in the H&H Report, the preliminary design has been updated. The key differences between the design in this H&H Report and the PDR are the treatment of the existing natural gas wells in west Area A and West Area B. Section 1.2 of this PDR describes these differences. Refinements to the hydraulic analyses will evaluate the current design in greater detail and will be included in Submittal B.

Sincerely,

A handwritten signature in blue ink, appearing to read 'Nicholas Garrity'.

Nicholas Garrity, P.E.
Southern California Manager / Project Manager
ESA PWA | Environmental Hydrology

TABLE OF CONTENTS

	<u>Page No.</u>
1. INTRODUCTION	1
1.1 BACKGROUND AND KEY ISSUES	1
1.2 FLOOD CRITERIA	1
1.3 SOIL CHEMSITRY	3
1.4 PUBLIC USES	4
1.5 EARTHWORK	4
1.6 PHASING	4
2. PRELIMINARY DESIGN	6
2.1 EXISTING TOPOGRAPHY AND UTILITIES	6
2.2 SOILS AND GEOTECHNICAL INVESTIGATIONS	7
2.2.1 Geotechnical Engineering Properties	8
2.2.2 Chemical Properties	9
2.2.3 Wetlands and Uplands Suitability (Agronomy)	10
2.3 NEW PERMETER LEVEES	11
2.3.1 Levee Crest Elevations	11
2.3.2 Levee Design Sections and Construction	14
2.3.2.1 North Area A Levee	15
2.3.2.2 Culver Levee	15
2.3.2.3 West Area B Levee	16
2.3.2.4 Temporary Area B Levee	17
2.3.3 Armoring	18
2.3.4 Existing Levee Improvements	19
2.3.4.1 Levee Tie-Ins	19
2.3.4.2 Ballona Creek Levees – Area A & B	19
2.3.4.3 Ballona Creek Levee - Area C and between Jefferson and Culver	19
2.4 BALLONA CREEK REALIGNMENT	20
2.4.1 Channel Sizing	20
2.4.2 Sinuosity	21
2.4.3 Armoring	21
2.4.4 Berms and Islands	21
2.4.5 Levee Breaching and Lowering	22
2.5 AREA A – TIDAL WETLAND, TRANSITION ZONE, AND UPLAND RESTORATION	22
2.5.1 Tidal Marsh	23
2.5.2 Salt Pans	24
2.5.3 Transition Zone and Upland	24
2.5.4 Seasonal Wetlands	24

2.6	AREA B – TIDAL WETLAND, TRANSITION ZONE, AND UPLAND RESTORATION	25
2.6.1	North Area B – Tidal Wetland, Transition Zone, and Upland	25
2.6.2	West Area B – Tidal Wetland, Transition Zone, and Upland	25
2.6.2.1	Interim Phase	25
2.6.2.2	Final Phase	26
2.6.3	South and East Area B – Managed Wetland Restoration and Enhancement	26
2.7	TIDAL CHANNELS	28
2.7.1	Area A	29
2.7.2	North Area B	29
2.7.3	East Area B	30
2.7.4	South Area B	30
2.7.5	West Area B	30
2.8	HYDRAULIC STRUCTURES	31
2.8.1	Culver Levee Water Control Structures	31
2.8.2	Freshwater Marsh Water Control Structures	31
2.8.3	Culver Boulevard Stormwater Management	33
2.8.3.1	Existing Conditions	33
2.8.3.2	Proposed Drainage Conditions	33
2.9	AREA B AND C UPLAND FILL PLACEMENT AND HABITAT RESTORATION	34
2.9.1	Area B – Upland Fill	34
2.9.2	Area C – Upland Fill	35
2.9.2.1	Area C North	35
2.9.2.2	Area C South	35
2.9.3	Seasonal Wetlands	38
2.10	NATURAL GAS STORAGE FACILITIES	38
2.10.1	Gas Infrastructure Decommissioning Plan	39
2.10.2	Interim Build Out Well Abandonment	40
2.10.3	Full Build Out	40
2.10.4	Pipeline Protection and Relocation	40
2.11	ENGINEER’S ESTIMATES	41
2.11.1	Earthwork Quantities	41
2.11.2	Cost Estimates	42
3.	CONSTRUCTION METHODS AND PHASING	48
3.1	CONSTRUCTION METHODS	48
3.1.1	Soil Transport	48
3.1.1.1	Across Ballona Channel	49
3.1.1.2	Across Roadways	50
3.1.2	Levee Lowering and Breaching	50
3.1.3	Soil Bearing and Construction Equipment	50
3.1.4	Tidal Channel Excavation and Earth Berm / Terrace Fill	51
3.1.5	Ballona Channel Realignment	51

3.1.6	Construction Period Levee Stability	52
3.1.7	Clearing and Grubbing and Invasive Plant Material Treatment	52
3.1.8	Revegetation	52
3.1.9	Gas Well Abandonment and Replacement Process	53
3.1.9.1	Site Preparation	53
3.1.9.2	Well Abandonment	53
3.1.9.3	Drilling New Well	54
3.1.9.4	New Well Completion Operations	55
3.1.9.5	Investigate and Remediate Contamination from Abandonment or Drilling of Gas Wells	56
3.2	CONSTRUCTION SEQUENCING	56
4.	OPERATIONS AND MAINTENANCE	59
4.1	EXISTING LA COUNTY O&M	59
4.2	BALLONA CREEK CHANNEL - MONITORING AND MAINTENANCE	60
4.3	PERIMETER LEVEES - MONITORING AND MAINTENANCE	60
4.4	WATER CONTROL STRUCTURES	60
4.5	HABITAT AND VEGETATION – MONITORING AND MAINTENANCE	60
5.	LIST OF ACRONYMS	61
6.	REFERENCES	62
7.	LIST OF PREPARERS	63

LIST OF APPENDICES

Appendix A	Existing Conditions/Survey
Appendix B	Preliminary Geotechnical Design Summary
Appendix C-1	Sediment Characteristics Sampling and Analysis Plan
Appendix C-2	Preliminary Assessment of Sediment Characterization of Areas A and B for the Ballona Wetland Restoration Project
Appendix D-1	West Area B Levee Alignments Memo
Appendix D-2	Levee Protection Memo
Appendix E	Construction Equipment Pictures
Appendix F	Construction Phasing Figures
Appendix G	Material Transport Routes
Appendix H	Public Access Bike Path
Appendix I	Local Drainage Hydrology
Appendix J	Miscellaneous Civil

LIST OF TABLES

Table 1	Coastal Water Levels and Datums
Table 2	Freeboard for Existing Conditions and Proposed Project
Table 3	Habitat Elevations
Table 4	Tidal Channel Dimensions by Channel Order
Table 5	Preliminary Estimates of Earthwork Volumes
Table 6	Preliminary Work Item Schedule
Table 7	Earthwork Transport Options
Table 8	Ballona Creek Crossing Methods
Table 9	Existing LA County O&M Activities and Anticipated Continuation of Existing O&M

LIST OF FIGURES

Figure 1	Ballona Wetlands Project Area
Figure 2	Existing Topography Map
Figure 3	Overall Existing Utilities Exhibit
Figure 4	Restored Habitat Zones
Figure 5A	Preliminary Grading Plan – Interim Build Out – Option A
Figure 5B	Preliminary Grading Plan – Interim Build Out – Option B
Figure 5C	Preliminary Grading Plan – Full Build Out
Figure 6	Perimeter Levees Plan
Figure 6A	Levee Sections Area A & Area B Culver Road
Figure 6B	Levee Sections Area B Culver Road & Area B West
Figure 6C	Artistic Rendering for Alternative B
Figure 6D	Perimeter Levee Armoring Plan
Figure 7	Ballona Creek Realignment Plan
Figure 7A	Ballona Creek Upstream Channel Sections
Figure 7B	Ballona Creek Downstream Channel Sections
Figure 8	Area A and North Area B Grading Plan
Figure 8A	Area A and Area B Grading Sections
Figure 9	Tidal Channel Network
Figure 10	Area B Triangle Proposed Grading Exhibit
Figure 11	Area C Proposed Grading Exhibit

1
2
3 **1. INTRODUCTION**

4 This Preliminary Design Report (PDR) documents the main project elements included in the Ballona
5 Wetlands Restoration Project (the Project) at the preliminary design level. The Project entails several key
6 design considerations and this PDR addresses these considerations in order to focus engineering efforts
7 toward completion of the project design.

8 1.1 BACKGROUND AND KEY ISSUES
9

10 The Ballona Wetlands Restoration Project (Ballona Project) entails expansion and enhancement of
11 wetlands adjacent to lower Ballona Creek, and associated site modifications necessary to avoid adverse
12 effects to surrounding property and interests. The project covers about 600 acres between Marina Del Rey
13 (to the north) and Playa Del Rey (to the south), and from about 2,000 feet east of the Pacific Ocean to
14 about 10,500 feet farther upstream along Ballona Creek (Figure 1; PWA and others, 2008).
15

16 The site is divided into several areas (See site plan: Figure 1):
17

- 18 • Area A: North of Ballona Creek and west of Lincoln Boulevard;
- 19 • Area B: South of Ballona Creek, subdivided into:
 - 20 ○ West Area B
 - 21 ○ South Area B
 - 22 ○ East Area B
 - 23 ○ North Area B
- 24 • Area C: North of Ballona Creek, east of Lincoln Boulevard, subdivided into:
 - 25 ○ North Area C, north of Culver; and,
 - 26 ○ South Area C, south of Culver (further subdivision for a visitors center may occur).
27

28 The project is progressing with simultaneous environmental review, design and permitting. The work is
29 being accomplished by a team consisting of several consultants, under several contracts (ESA PWA,
30 2012a).
31

32 1.2 FLOOD CRITERIA
33

34 The project entails realignment of flood control levees subject to approval by the US Army Corps of
35 Engineers and Los Angeles County (ESA PWA, 2012b). The governing flood source is Ballona Creek
36 when high flows resulting from rainfall in the tributary watershed increase flowrates toward the ocean.
37 The project flood control objective is to provide an equivalent or increased level of flood protection
38 relative to existing conditions.
39

40 The LA District Corps of Engineers' Operation and Maintenance Manual identifies the design capacity as
41 46,000 cfs with a minimum of two feet of freeboard based on the original 1935 Corps channel design.
42 However, more contemporary flood management criteria may need to be applied as the result of
43 permitting and other requirements, even if the new criteria represent an “upgrade” relative to the original

1 design and/or the existing level of flood protection. Flood flows with and without project, including
2 anticipated future sea levels, have been modeled in a separate Ballona Wetlands Restoration Project
3 Preliminary Hydrology and Hydraulics Report (H&H Report) (ESA PWA, 2013).

4
5 The site overlays a deeply buried natural gas storage facility. Associated with this facility are near-surface
6 and surface features in the site. Removal of much of these facilities is expected, and the preliminary
7 design is configured to address the most likely scenario (extent of facility removal) based on discussions
8 with the Gas Company. Still, there remains uncertainty about the timing of gas monitoring well removal
9 (also called “abandonment” even though the near surface components are completely removed) in Areas
10 A and B. Therefore, the preliminary design includes two options for removing the wells in Area A: one in
11 which the wells remain in the initial phase of the restoration (Option A shown in Figure 5A) and one in
12 which the wells are removed for the initial phase (Option B shown in Figure 5B).

13
14 Note that the H&H Report assesses a prior iteration of the design that is similar to the current design
15 presented in this PDR. Since the completion of analyses in the H&H Report, the preliminary design has
16 been updated. The key differences between the design in the H&H Report and this PDR are the treatment
17 of the existing natural gas wells in west Area A and West Area B. The Interim Build Out - Option A
18 condition depicted in Figure 5A is consistent with the modeled condition and results reported in the H&H
19 report. In West Area B, the current Full Build Out condition in this PDR shows the upland habitat
20 peninsula as a smaller feature, but with a similar functional intent as modeled in the H&H report. We
21 anticipate updating the modeling subsequent to Submittal A.

22
23 The elevations in Area B and some adjacent properties are below flood levels, and tributary properties
24 rely on Area B for storm runoff storage (ESA PWA, 2012b). Area B currently receives limited tidal
25 circulation and drains to Ballona Creek through the existing tide gates. Tributary areas adjacent to Area B
26 rely on the site to accept local rainfall runoff without backing up onto developed areas. These drainage
27 ways are:

- 28
29 • Freshwater Marsh (FWM) for Playa Vista (East Area B); Depending on the water surface
30 elevation maintained in it, the FWM is designed to overflow into south area B above a 1 to 2 year
31 rainfall runoff event for the Playa Vista development. Therefore, the water level in Area B must
32 not exceed the overflow weir at FWM, and the high water level in Area B must be low enough to
33 accommodate overflow from FWM.
- 34 • Playa del Rey (West Area B); The area of Playa del Rey at the southwest corner of Area B
35 experiences localized flooding under some circumstances. This is a symptom of poor drainage for
36 this area in a sump condition. The project concept now includes allowing an area for a storm
37 water detention basin on the inboard (Playa del Rey) side of the new levee.
- 38 • Roadways (Area B); The Culver and Jefferson roadways in Area B are low in elevation and close
39 to groundwater. There is a ground water infiltration gallery at the intersection of these two roads.
40 Hence, the low area of roadway is along Culver, west of the junction with Jefferson. Earth berms
41 may be required to reduce the risk of high water flooding, along with the installation of
42 conveyance and storage channels, culverts and tide gates.

- Gas Company facilities (primarily Area B, but also west Area A); There are industrial facilities in south Area B that are constructed on fill but are low enough to be flooded under some higher tidal waters.

Water control structures are being designed to enhance wetland ecology in South Area B through increasing tidal exchange. These new culverts will replace existing culverts. Both existing and new culverts will include gates to limit high water. Other actions such as berms and new channels may be included as part of the enhancement. The existing culverts serving Area B have self-regulating-tide-gates and provide a very useful example for consideration.

The coastal flood sources (high tides, storm surge, surface waves and tsunamis) are not expected to govern levee design since these water levels are lower than the fluvial design water levels (i.e., lower than the flood levels associated with rainfall-runoff storm events and resulting Ballona Creek flows).

Sea level is expected to rise at an accelerated rate. Relative sea level rise is the addition of vertical land motion with sea level change. The restoration and flood management approach would consider the effects of future sea-level rise (per the California Governor's Executive Order S-13-08 and the State Coastal Conservancy's Climate Change Policy adopted June 4, 2009) (ESA PWA, 2012b). The restoration is being designed to accommodate future accelerated sea level rise scenarios. This may involve either constructing new levees to higher elevations or constructing levees that can easily accommodate future elevation increases based on actual sea level rise.

A report addressing sea level rise for the west coast of the continental US was just released (NAS, 2012), and will be used to update the State's interim guidance. The new sea level rise estimates are similar to the interim guidance, except for a slightly lower "maximum" rise by the year 2100. United States Army Corps of Engineers recently re-issued federal agency guidance that is currently consistent with that of the State of California (USACE, 2011). This guidance document requires consideration of several sea level rise scenarios forming a range of sea level rise acceleration. These sea level rise scenarios are similar to the State guidance documents, and we anticipate selection of scenarios that satisfy both State and Federal requirements. In the mean time, we use the more conservative USACE (2011) estimate and assume that sea level rise will amount to approximately 59 inches by 2100.

1.3 SOIL CHEMISTRY

As part of the site reconnaissance and assessment, tests are being conducted to determine the location and concentrations of potential sources of soil contamination. They will guide specific construction techniques, sediment removal, and sediment management. While the site has a history of uses that may have introduced contaminants, the existing data indicate that the earth to be excavated can be reused on site, with select materials used in surface and habitat areas.

The use history includes agriculture, oil drilling and natural gas storage. In addition, the soil chemistry below previously filled areas may be affected by low oxygen levels or limited organics. The soil chemistry is important from the perspectives of appropriate sequestration in fill areas, biological uptake in

1 restored areas, and vegetation establishment. A detailed field exploration effort has been undertaken to
2 investigate the chemical properties of the soils to be excavated and those to be at or just below the
3 anticipated finished grades. The data collection plans and observations during sampling are provided in
4 Appendix B. Pending completion of the laboratory testing and interpretation, we anticipate that soil
5 chemistry is consistent with storage in fill areas, and that offhaul of material due to contamination is not
6 required. Also, we will evaluate the benefit of soil amendments or backfill with selected soils to enhance
7 vegetation establishment and wetland ecology.

8 9 1.4 PUBLIC USES

10
11 Existing public uses will be accommodated and/or mitigation will be provided. Culver Boulevard,
12 Jefferson Boulevard and Lincoln Boulevard (State Highway One) traverse the project site and will be
13 maintained. A gas storage facility in south Area B is accessed from these roads, and there are multiple
14 monitoring wells and several pipes within the project limits. Public access exists along the north Ballona
15 Creek levee on a County maintained bike path all other public access is only allowed by issuance of an
16 access permit from the Department of Fish & Game.

17
18 A public access plan is being developed to maintain existing uses and provide additional access
19 opportunities. Anticipated elements, such as a pedestrian bridge across Ballona Creek are included in this
20 preliminary design. Also shown in the preliminary design is parking and access at the southwest corner of
21 Area B, where existing parking and trails are heavily used. Other elements, such as a visitor center and
22 parking, are anticipated but not sufficiently developed to include in the preliminary drawings.

23 24 1.5 EARTHWORK

25
26 The Project will entail movement of between one and two million cubic yards of earth. Earth movement
27 between Areas will require crossing roads (Lincoln and possibly Culver in Areas A and C; and Culver
28 and/or Jefferson in Area B), and crossing Ballona Creek. The project also includes re-alignment of
29 Ballona Creek, which will entail construction of new channel segments and filling of existing channel
30 segments. Construction is expected to take several years and consist of several phases. The intent is to
31 balance earthwork on site with placement in Areas B and C.

32 33 1.6 PHASING

34
35 Earthwork and restoration will occur in several phases. These phases are described in more detail in
36 Section 3 of this report. Broadly, the construction phases include:

- 37
38 1. Phase 1 will involve excavation in Area A and construction of new levees around the enhanced
39 wetland areas in Areas A and B. This phase is expected to require 2 to 4 years.
40 2. Phase 2 will involve excavation of new meander bends for Ballona Creek, breaching the existing
41 Ballona Creek Levees, and filling in Ballona Creek within the meander bends. The completion of
42 this phase restores full tidal action to Area A and North Area B. This is referred to as the
43 “Interim Project” because the project site will remain in this interim state for a period of years

- 1 while habitat establishes in Area A and North Area B. Note that the preliminary design includes
2 two options for the “Interim Build Out:”
- 3 a. Option A: if the gas wells in west Area A are not removed prior to the Interim Build Out, the
4 area around the wells will remain at existing grade and the wells will be protected in place.
 - 5 b. Option B: if the Area A gas wells are removed as part of the Interim Build Out, the area
6 around the wells will be excavated to create restored wetland, transition zone, and upland
7 habitats.
- 8 3. Phase 3 involves restoring tidal action to West Area B by lowering and breaching the remaining
9 Ballona Creek levee at West Area B. This phase will commence once the restoration of Area A
10 and North Area B meets the performance criteria set forth in the environmental documents,
11 permits, and an Adaptive Management Plan.

1 **Table 1 Coastal Water Levels and Datums.**

	MLLW	NAVD	NGVD
	(ft)	(ft)	(ft)
100-year tide (FEMA)	9.1	8.9	6.5
Max. observed (11/30/1982 7:54)	8.5	8.3	5.9
HAT (12/2/1990 16:12)	7.3	7.1	4.6
MHHW	5.4	5.2	2.8
MHW	4.7	4.5	2.1
MTL	2.8	2.6	0.2
MSL	2.8	2.6	0.2
NGVD	2.6	2.4	0.0
MLW	0.9	0.7	-1.7
NAVD	0.2	0.0	-2.4
MLLW	0.0	-0.2	-2.6
LAT (1/1/87 0:00)	-2.0	-2.2	-4.6
Min. observed (12/17/1933 15:42)	-2.8	-3.0	-5.5

- 2 Notes: Tidal datums from NOAA/NOS Santa Monica Tide Station 9410840, 1983-2001 Epoch
3 NAVD to NGVD conversion from NOAA/NGS
4 100-year tide from FEMA (2008) Flood Insurance Study for Los Angeles County (based on studies completed in 1984)
5 HAT = highest astronomical tide
6 MHHW = mean higher high water
7 MHW = mean high water
8 MTL = mean tide level
9 MSL = mean sea level
10 MLW = mean low water
11 MLLW = mean lower low water
12 LAT = lowest astronomical tide
13 NAVD = North American Vertical Datum of 1988
14 NGVD = National Geodetic Vertical Datum of 1929
15

16 **2.2 SOILS AND GEOTECHNICAL INVESTIGATIONS**

17
18 The majority of construction involves earthwork, primarily excavation to realign Ballona Creek and to
19 create tidal marsh and transitional habitat in Area and fill to build new engineered flood control levees set
20 back from the Ballona Creek channel. Therefore, the geotechnical and engineering properties, levels of
21 chemicals and metals, and general agronomy are key soil properties to understand when developing
22 earthwork plans.
23

24 The project is performing geotechnical investigations and sampling and analysis for chemicals, metals
25 and general agronomic properties to inform design decisions to optimize the use of soils at the project
26 site.
27

1 2.2.1 Geotechnical Engineering Properties

2 The project Geotechnical Engineer, Group Delta, is performing a geotechnical investigation and analyses
3 to develop design and construction recommendations for the new flood control levees and to examine
4 stability of existing levees. The geotechnical investigation includes a field program with soil borings to
5 collect samples for laboratory analysis and Cone Penetration Testing (CPT) in areas of the new proposed
6 levees, near existing levees, and within areas of planned excavation to inform design level geotechnical
7 analysis. The field program and laboratory analyses were performed starting in September 2012. The
8 design level geotechnical report is anticipated in June 2013.

9
10 The primary engineering soil parameters that will affect earthwork include:

- 11
- 12 • Grain size, fraction of organics
- 13 • Bulk density, moisture content and volume change with compaction
- 14 • Shear strength, plasticity
- 15 • Permeability
- 16 • Seismic response, liquefaction potential
- 17 • Consolidation, settlement
- 18 • Slope stability, bearing capacity
- 19 • Active / passive pressure
- 20 • Other (existing levee stability, offsets for excavation adjacent to existing levees, etc.)

21
22 To help inform preliminary design, Group Delta provided a Preliminary Geotechnical Design Summary
23 based on available data taken from previous studies (provided in Appendix B). The available data are not
24 sufficient to support current requirements for final design. There were significant areal gaps in the
25 previous borings and also primarily addressed physical properties rather than the engineering properties
26 of the site soils. Thus, the preliminary report provided provisional assessments based upon conservative
27 assumptions and limited available data.

28
29 Materials for construction of the new perimeter levels will be primarily excavated from Area A. Soils
30 within Area A are layered reflecting the placement of hydraulic dredge material from the construction of
31 the adjacent Marina del Rey in the upper 10 to 15 feet underlain by native silts. The hydraulic fill
32 primarily consists of inorganic, low plasticity silts and silty sands with some lean clay and elastic silts. In
33 general, this material is anticipated to be acceptable for levee construction.

34
35 The Preliminary Geotechnical Design Summary provided provisional analysis of the static stability and
36 dynamic loading of the proposed and existing levees. In addition, estimates of the anticipated settlement
37 of the new levees and seepage rates for work near Ballona Creek were provided.

38
39 The preliminary analyses indicated that the proposed levees provided adequate Factors of Safety for both
40 static and dynamic conditions for the loading conditions analyzed. The design approach based on the
41 preliminary geotechnical recommendations for specific levee sections are described below in Section
42 2.3.2.

1 2.2.2 Chemical Properties

2 The project site has a history of oil and gas exploration. Previous investigations in Area A performed by
3 Weston Solutions for the Port of Los Angeles in 2008 indicated that the soils were non-hazardous in the
4 areas tested and therefore suitable for upland placement. However, there were levels of iron and arsenic
5 that, while consistent with ambient concentrations in marine sediments, exceeded residential California
6 Human Health Screening Levels in a number of samples. There was also one sample that exceeded the
7 human health screening level for benzo [a] pyrene (39.7 ug/kg vs 38 ug/kg) for residential use. In
8 addition, soil samples from several locations had elevated photoionization detector (PID) readings,
9 however none of the samples analyzed for petroleum hydrocarbons exceed human health screening levels.

10
11 Several samples slightly exceeded the low range ER-L screening levels for ocean disposal of dredge
12 material for metals (including Arsenic, Cadmium, Copper, Lead, Mercury, Nickel, and Silver), however,
13 no samples had metals concentrations above the medium range ER-M screening level. One sample
14 exceeded the ER-L for organochlorine pesticide 4,4 DDE.

15
16 To help determine if specific soils at the project site would be suitable for upland and/or wetland material
17 within the restoration project, Weston Solutions developed a Sampling and Analysis Work Plan (SAP) to
18 further characterize sediments to be excavated from Area A and Area B (Attached in Appendix C). The
19 SAP provides for both discrete and composite sampling with analysis for general chemistry, organics,
20 inorganics, and petroleum hydrocarbons (if samples exhibit staining or register on PID analysis). In
21 addition, at select locations at the design surface elevation, bioassays are planned to help assess the
22 suitability of the material for wetland cover. The SAP provided screening tools and guidelines that will be
23 used to assess the suitability of onsite soils for use as:

- 24
25 • Wetland Cover Material – materials that meet the regulatory requirements for wetland cover
26 based on ER-M screening and bioassay results (pending regulatory review and approval).
27 Wetland cover may be used anywhere on site, but will be prioritized for use in the upper three
28 feet of the channel and wetland surface.
- 29 • Upland Cover Material – materials that meet the human health screening levels, but exceed
30 wetland cover standards. Upland cover material would be used for any upland placement or
31 below three feet of wetland cover material within the channels or wetland surface.
- 32 • Non-Hazardous Material – materials that are below the state and federal thresholds for hazardous
33 waste (Title 22), but exceed the human health screening levels. Non-hazardous material may be
34 placed in upland areas (levees and soil mounds) capped with a minimum of three feet of upland
35 cover material.
- 36 • Hazardous Materials – materials that exceed the state and federal thresholds for hazardous waste
37 (Title 22) will be disposed of offsite.

38
39 Soil samples were collected for analysis under the SAP in conjunction with the geotechnical borings in
40 September and October, and analysis results are expected in November 2012.

41
42 Preliminary observations during sampling indicate that some petroleum contamination was observed in
43 the following locations:

- 1 • Area A – Proposed Channel alignment. A petroleum odor and dark staining was noted about 10-
2 14 feet below ground surface (bgs). The impacted sediment was limited to about a 2 to 4 feet
3 thick layer. Samples were collected for analysis from the impacted layer and just above and
4 below to further characterize the area. The impacted layer is within the planned excavation depth
5 for the realigned creek, i.e. the creek surface would be below the impacted layer.
- 6 • Area A – Marshplain & Transition Zone. North east of the existing gas wells at the west end of
7 Area A (Del Rey 14), a petroleum odor and staining was noted about 10.5 feet bgs (near the
8 planned marsh/transition surface). The odor and staining was limited to about a 1.5 feet thick
9 layer near design grade.
- 10 • Area B – Proposed Channel and Marshplain. In borings in the vicinity of the existing gas wells in
11 Area B a petroleum odor and staining was noted between 6-6.5 feet bgs near gas well Del Rey 12
12 relatively close to design grade. A less significant odor and staining was noted 4-8 feet bgs from
13 within the planned channel alignment through Area B.

14
15 Laboratory analysis results will provide more detailed data at these and other sample locations.

16
17 These preliminary findings indicate that in some areas within the planned wetland habitat, materials that
18 do not meet the wetland cover standards may be present. In these areas, materials that are not suitable for
19 wetland cover will likely be over excavated and replaced with soil selected to be appropriate for a
20 wetland. Another measure under consideration is application of soil amendment to improve soil
21 chemistry.

22
23 Based on this limited data, the project may anticipate over-excavation and replacement of up to 50,000 to
24 100,000 cubic yards (CY) of material.

25 26 2.2.3 Wetlands and Uplands Suitability (Agronomy)

27 In conjunction with the chemical and geotechnical sampling, sediment samples are also being analyzed
28 for general agronomic characteristics. The ability for plants to establish rapidly is associated with the soil
29 chemistry. Since the excavated finished grades are well below the existing ground surface in Area A, the
30 chemistry may not be conducive to plant establishment.

31
32 Agronomy tests include analyses for soluble and exchangeable major nutrients, boron, USDA texture,
33 organic matter, micronutrients, and neutralization/acid generation potential. These analyses are intended
34 to identify general soil parameters that may impede the establishment of marsh and upland transition
35 vegetation at the site or other factors that may impact the evolution of the site to support a healthy mosaic
36 of vegetated habitat. These tests will inform decisions on the need to identify select materials from the
37 project site for use as “top soil” or the potential need to augment the post-construction surface soils to
38 address nutrient or organic matter deficiencies.

1 2.3 NEW PERMETER LEVEES

2
3 A primary project element includes replacing the existing Ballona Creek levees with new engineered
4 flood control levees set back from Ballona Creek. The proposed levees will be engineered to meet or
5 exceed current flood control standards.

6
7 The proposed flood control levees are shown on the levee plan presented on Figure 6.
8

9 2.3.1 Levee Crest Elevations

10 The H&H Report has performed hydraulic modeling to estimate water surface elevations along the project
11 site for a number of flood events including the design flow rate for Lower Ballona Creek (46,000 cfs)
12 cited in the LA District Corps maintenance manual (USACE 1999) with a variety of tail water conditions
13 including the LA County design tail water of 7.6-feet NAVD. Hydraulic modeling has been performed for
14 the existing channel conditions (based on recent survey by PSOMAS) and for the preliminary grading
15 plans presented in Figures 3, 5a - 5c respectively. The hydraulic modeling approach, methods, and results
16 are presented in detail in the H&H Report.
17

18 Existing conditions model results are presented below in Table 2. Table 2 provides the estimated
19 freeboard at a number of locations along the project site. Freeboard for existing conditions along Area
20 A/North Area B ranges from 5.01 to 6.46 feet and averages 5.85 feet. Along the West Area B reach,
21 freeboard ranges from 3.08 to 3.84 and averages 3.49. Freeboard was also estimated for the existing
22 channel configuration for the Year 2100 sea level rise scenario with the downstream tailwater increased to
23 account for 4.6 feet of sea level rise. Accounting for sea level rise, freeboard dropped to an average of
24 2.62 feet along Area A and -0.45 feet along West Area B (indicating that the levees would over top for the
25 design event).
26

27 One design objective for the new proposed flood control levees is to provide a similar level of freeboard
28 for the design flood event both with current tail water elevations and with tail water elevation adjusted for
29 predicted sea level rise by year 2100 based on Coastal Conservancy Policy and USACE guidance (7.6
30 feet NAVD + 4.9 feet of sea level rise).
31

32 Proposed conditions model results for estimated freeboard are also presented in Table 2. Note that these
33 results are from the H&H Report and a prior iteration of the design as described in Section 1.2. At the
34 preliminary design level, the perimeter levees have been designed with a constant levee crest of EL 20.5
35 feet NAVD. The hydraulic modeling was run against the current design tail water elevation for both the
36 Interim Project design scenario with West Area B remaining as managed marsh habitat and with the Full
37 Restoration scenario after West Area B becomes fully tidal. Along Area A/North Area B, the Interim
38 Project (conditions similar to Option A), provides between 6.01 and 7.88 feet of freeboard with an
39 average of 6.36 feet of freeboard (about a 0.3 feet increase over existing conditions). Along West Area B,
40 freeboard ranges from a low 7.97 feet to 10.7 feet in West Area B and averages 9.76 feet along the reach.
41 Under the Full Project scenario, freeboard increases to an average of 6.79 along Area A/North Area B and
42 9.37 along West Area B. For the Year 2100 sea level rise scenario, the proposed project increases
43 freeboard to an average of 4.06 feet along Area A/ North Area B and 5.51 feet along West Area B.

1 For West Area B, model results show significant increases in freeboard for the Left Bank under project
2 conditions, reflecting the increased levee heights proposed for West Area B. Through most of this reach,
3 however, the Right Bank consists of the existing levee/jetty that is not shown as being modified under the
4 preliminary project design. Elevated water levels in the vicinity of Area B under project conditions reduce
5 the amount of freeboard provided by the existing levee/jetty along the Right Bank by up to one foot. The
6 majority of the Right Bank is formed by the jetty that separates Ballona Creek from the Marina Del Rey
7 and a reduction in freeboard along the jetty may not represent a significant increase in flood risk.
8 However, as discussed in Section 2.3.2.1, there is a section of the existing levee between the upstream end
9 of the jetty and the downstream end of the new proposed North Area A levee that may need to be raised
10 in order to maintain or improve the existing level of flood protection.

11
12 Based on the preliminary H&H Report, estimated freeboard increases at the downstream project limits
13 (with the exception noted in the preceding paragraph). During later design phases, following a full risk
14 and uncertainty analysis, the levee heights may be refined and lowered to provide adequate freeboard to
15 meet the requirements of the US Army Corps of Engineers, LA County, and FEMA for the Year 2100 sea
16 level rise tail water levels.

Table 2 Freeboard for Existing Conditions and Proposed Project

Design Flood (46,000cfs)	Freeboard (ft)											
	Area A/B North (RS 6079 to 10019)						West Area B (RS 3055 to 5853)					
	Reach Average	Left Bank		Right Bank			Reach Average	Left Bank		Right Bank		
		Maximum	Minimum	Reach Average	Maximum	Minimum		Maximum	Minimum	Reach Average	Maximum	Minimum
Existing Conditions ¹	6.22	6.68	5.35	5.70	6.27	5.01	3.63	3.84	3.48	4.94	6.43	4.11
Existing Conditions w/ SLR ^{1,2}	3.17	4.10	1.71	2.65	3.33	1.37	-0.34	0.19	-0.76	0.97	2.78	-0.22
Interim Project ³	6.32	7.88	5.97	6.38	7.88	6.01	3.63	3.84	3.48	5.99	9.35	3.91
Full Project ⁴	6.76	8.47	6.33	6.70	7.97	5.95	9.15	10.60	8.65	5.11	8.70	3.01
Full Project w/ SLR ^{2,4}	4.02	4.90	3.81	3.97	4.64	3.33	5.28	6.73	4.95	1.24	5.00	-0.76

¹ Existing conditions freeboard is the difference between the predicted water surface and the existing levee elevation based on 2012 surveys.

² SLR = Sea level rise of 59 inches.

³ Interim project conditions freeboard along Area A/B North is the difference between the predicted water surface and a flat levee crest of EL 20.5 ft NAVD included for the preliminary design for the proposed levees. Along West Area B, interim project conditions freeboard is the difference between the predicted water surface and the 2012 surveyed elevation of existing levees to remain in the interim phase..

⁴ Full project conditions freeboard is the difference between a flat levee crest of EL 20.5 ft NAVD and the predicted water surface, except for the right bank along West Area B where the existing levee elevation was assumed for preliminary design analyses (see discussion in Section 2.3.2.1).

1 2.3.2 Levee Design Sections and Construction

2 Preliminary levee design sections for the proposed new flood control levees are provided on Figures 6A
3 and 6B. In general, the proposed levee designs include a compacted core constructed of low permeability
4 material with a wide flat slope along the Ballona Creek channel side of the levees that would serve as a
5 stability berm. The preliminary design for the compacted core incorporates 2H:1V slopes on the dry side
6 and flatter 3H:1V slopes on the creek side. Subgrade preparation varies based on location and material,
7 and is described for each levee reach below.
8

9 On the creek side, the outboard stability berms are shown with flat 10H:1V slopes. These slopes are
10 intended to support vegetated habitat including low high marsh plantings and upland transitional
11 plantings. The slopes would provide a wide flat bench to dissipate wind-waves and to protect the levee
12 core from erosion. As the design progresses, the idealized 10H:1V slope will be refined to provide a more
13 complex shoreline. At the western margins of the site, these slopes may incorporate sandy dune features
14 to support sand dune habitat. Along the eastern, upstream reaches, the slopes would be graded to provide
15 more of an undulating shoreline with variation in both steepness and elevation.
16

17 Armoring of the new flood control levees would vary, as described below, incorporating rock (or
18 concrete) on the levee face in areas of high velocity and erosion potential, to buried rock or soil cement in
19 areas of moderate erosion potential, to vegetation in areas where the levees are separated from the creek
20 channel by hundreds of feet with very gradual slopes.
21

22 The new perimeter levees would also support an access road that will serve as access for LA County
23 inspections and maintenance and provide public pedestrian and bicycle paths.
24

25 General geotechnical recommendations provided in the Preliminary Geotechnical Design Summary,
26 include:
27

- 28 • Subgrade preparation including removal of vegetation and soft unsuitable materials, over-
29 excavation, and compaction.
- 30 • Over-excavation and removal of abandoned utility lines.
- 31 • Removal of any standing water from the excavated subgrade, back fill and compaction to at least
32 90%.
- 33 • Construction of levees slowly with fill placement in thin layers, moisture conditioned, and
34 compacted with total compacted lift thickness of no more than 6-inches.
- 35 • Slow construction in lifts will tend to reduce post construction settlement. As the preliminary
36 design moves toward final design, the project will consider post construction settlement and
37 adjust design height as needed to account for anticipated settlement.
- 38 • Lifts shall be placed along the entire length of the levee prior to placement of the following lift.
- 39 • Compaction testing for every 500 cubic yards of fill or two feet of thickness.
40

41 Specific features for the each levee reach are described below.
42

1 2.3.2.1 *North Area A Levee*

2 The preliminary plan layout for the North Area A levee is shown on Figure 6 and a typical preliminary
3 levee design section is presented in Figure 6A. The proposed North Area A levee would tie into the
4 existing Ballona Creek levee at Culver Boulevard at the upstream limit of the marsh restoration area. The
5 proposed levee would follow the perimeter of Area A with a minimum 30 feet offset from Fiji Way and
6 Lincoln Boulevard and set just south of the Fiji channel. The proposed levee will be offset 20 feet to
7 maintain the existing parking lots along Fiji Way and to avoid existing natural gas monitoring well, Del
8 Rey 17.

9
10 The Preliminary Design and grading plans show the downstream end of the new North Area A levee tying
11 into the existing levee at the west end of Area A. Preliminary hydraulic modeling shows about a 1'
12 increase in the design flood water surface profile downstream of this location, and an equivalent reduction
13 in freeboard for the existing north levee/jetty downstream of Area A (i.e., along West Area B; see the
14 H&H Report, Section 3.3). The design will therefore consider extending the North Area A levee
15 downstream along a section of the existing north levee/jetty (i.e., raising a section of the existing north
16 levee/jetty downstream of Area A) as needed to maintain or improve the level of flood protection for
17 development at the end of Fiji Way.

18
19 In Area A the new proposed flood control levee is generally located 800 to 1200 feet from the realigned
20 Ballona Creek channel. The levee incorporates an idealized 10H:1V slope from the EL 20.5 feet crest
21 down to EL 11.0 feet. Below EL 11.0 feet, the levee gradually slopes down to the Area A tidal wetlands
22 basins at EL 5.0 with a gradually varying flat transitional slope from 40:1 to 150:1. This wide flat slope
23 will support dense wetland and transitional vegetation which is will protect the levee core from higher
24 velocity flows in the main Ballona Creek channel.

25
26 Area A is comprised of 15 to 25 feet of loosely consolidated dredge material from the excavation of
27 Marina del Rey above historic Ballona marsh soils. Given the unconsolidated existing materials, subgrade
28 preparation will be particularly important in Area A. Subgrade preparation in Area A is anticipated to
29 include:

- 30
31 • Removal of existing vegetation and over-excavation to a depth of 4 feet below grade.
32 • Along the levee core, over-excavation may be extended down to 6 feet below grade to provide a
33 keyway.

34
35 Hard rock or soil cement armoring is not planned for most of the Area A perimeter levee due to the wide
36 flat slopes and tidal wetland basins between levee and creek channel.

37
38 2.3.2.2 *Culver Levee*

39 Plan view layout of the Culver levee is shown on Figure 6 and design sections are presented on Figure 6A
40 and 6B. The Culver Levee extends from the south end of the Culver Boulevard Bridge where it ties in to
41 the existing Ballona Creek levee along Culver Boulevard to West Area B.

42 The Culver Levee included three distinct design sections:
43

- 1 • A wide plateau at the upstream limit between Culver Boulevard and the old railroad alignment.
2 This wide section is intended to vary the widening of the restored Ballona Creek floodplain to
3 help even out the hydraulic drop of flood levels as flood flows enter the Ballona Wetlands
4 Restoration Project site.
- 5 • A narrow section (20 feet top width) along Culver Boulevard to the intersection with Jefferson
6 Boulevard.
- 7 • A wide section (100 feet top width) along Culver Boulevard from Jefferson Boulevard to West
8 Area B.

9
10 The levee core would be located adjacent to Culver Boulevard, and the wider sections would support
11 vegetated habitat closer to Ballona Creek. Beyond the levee top, each section incorporates a flat idealized
12 10H:1V slope down to EL 6.5 ft with a flatter 20H:1V transitional slope to the adjacent tidal marsh plain.
13

14 In Area B, the subgrade is generally comprised of historic marsh soils, which are relatively close to
15 groundwater. Preliminary plans for subgrade preparation for the Culver Levee incorporate:

- 16
17 • Removal of existing vegetation and over-excavation to a depth of 2 feet below grade.
- 18 • Along the levee core, over-excavation may be extended down to 4 feet below grade to provide a
19 keyway.

20
21 Armoring including either buried rock or soil cement would be utilized along the Plateau and Narrow
22 sections of the levee where the levee is within (200 to 800 feet of Ballona Creek. Armoring is not planned
23 in the Wide section where the levee core would be separated from Ballona creek by at least 80 feet of
24 vegetated high ground.
25

26 2.3.2.3 *West Area B Levee*

27 The preliminary layout for the West Area B Levee is shown on Figure 6 and a typical design section is
28 shown on Figure 6B. The alignment of the West Area B Levee has been updated from the previous
29 conceptual design. First, the levee has been shifted north to avoid existing natural gas monitoring well
30 Vidor 18. Second, after considering a number of potential alignments along the western limits of the
31 project site, the levee was shifted to the east through the existing marsh. The considered alignments and
32 the analysis for each alignment described in detail in the levee alignment memorandum included in
33 Appendix D-1.
34

35 Along the west end of the project site, the conceptual alignment included use of existing high ground to
36 provide flood protection. While this high ground was at an adequate elevation, the area is comprised of a
37 former sand dune which introduced a number of concerns related to flood protection:

- 38
39 • A former sand dune would be subject to liquefaction limiting seismic stability.
- 40 • The sand dune would permit seepage, potentially impacting adjacent properties.
- 41 • Installing a cutoff wall to address seepage impacts could cause vibration impacts to adjacent
42 properties.
- 43 • The sand dune could be subject to erosion, potentially leading slope stability impacts.

- 1 • Use of the dune would limit the ability of the County to traverse the length of the levee for
2 inspection and maintenance.
- 3 • Placing an engineered levee/access road along the dune to provide for County access, could lead
4 to impacts to adjacent properties due to excavation, fill and compaction activities causing
5 differential settlement at adjacent properties on sand subsoils.
- 6 • Also an engineered levee/ access road would impact adjacent high-value dune habitat to the east.
7

8 To address these concerns, the levee was realigned to the east of the existing high-value dune habitat
9 along the western edge of the managed marsh habitat in West Area B.

10
11 The West Area B levee includes an idealized 3H:1V slope along the existing dunes to the west and a
12 10H:1V slope down to the existing managed marsh to the east. Along the existing dunes, the project plans
13 to create additional dune habitat along the levee shoulder. Along the wetland side of the levee, the
14 transitional slope would vary to create a natural undulating shoreline. An artist's rendering of the West
15 Area B levee is provided in Figure 6C and the design section showing the topographic variation is
16 presented in Figure 6B.

17
18 Similar to the Culver levee, the West Area B levee will be constructed on historic marsh soils with high
19 groundwater. In addition the West Area B levee will cross existing channels in several locations.
20 Subgrade preparation is anticipated to include:

- 21 • Removal of existing vegetation and over-excavation to a depth of 2 feet below grade.
- 22 • Along the levee core, over-excavation may be extended down to 2 to 4 feet below grade to
23 provide a keyway.
- 24 • At channel crossings, the channels will be blocked on either side of the levee core and dewatered.
25 Loose, unsuitable material will be over excavated and the channel area will be rebuilt with
26 compacted fill.
27

28
29 West Area B will be primarily a backwater area during flood events, and erosion potential is expected to
30 be limited along most of the levee reach. Therefore, we anticipate that armoring will be limited to the
31 downstream most reach of the levee. We expect to use rock facing at the tie-in to the existing Ballona
32 Creek South levee transitioning to buried soil cement or rock protection of the levee core along the
33 downstream most reach of the levee.

34 35 *2.3.2.4 Temporary Area B Levee*

36 The project will be phased with full restoration of West Area B delayed for a number of years until the
37 restoration in Area A demonstrates success. During this interim period, a temporary levee will connect the
38 Culver Levee to the existing Ballona Creek South Levee just north of the existing natural gas monitoring
39 well cluster in West Area B. This temporary levee is shown on the levee plan in Figure 6 and in section
40 on Figure 6B. This temporary levee is constructed with steeper 5H:1V side slopes on the Ballona Creek
41 side. Subgrade preparation will be similar to the Culver and West Area B levees discussed above.
42

1 The Temporary Levee will incorporate buried rock or soil cement armoring along much of its length.
2 Rock facing is planned at the tie in with the South Ballona Creek levee, the project anticipating using.

3 4 2.3.3 Armoring

5 Armoring of the existing side slopes of the Ballona Creek consists of two types, concrete and rock.
6 However, the new flood control levees will be set back away from the Ballona Creek channel. The
7 additional flow capacity provided by the setback levees and the resulting reduction in flow velocities and
8 shear stresses provide opportunities to utilize alternative measures for levee protection.

9
10 With the primary intent of the project being to create and restore habitat, it is the intent to keep the use of
11 traditional armor, and especially concrete, to a minimum. Where flow velocities and scouring potential
12 allow, we plan to use vegetation to armor the levees. Where additional risk is identified, the priority for
13 levee armoring is a levee core consisting of compacted and stabilized soil with a protective cladding of
14 either rock or soil cement, covered by less compacted soils that allow planting and habitat establishment.
15 The typical levee cross-sections for Area B presented on Figures 6A and 6B illustrates this approach.
16 Along Area A, where the perimeter levee is set back from Ballona Creek by 800 to 1200 feet, the
17 preferred armoring method would be to rely upon vegetation established on the flat, vegetated transitional
18 slopes (100:1 sloping up to 40:1 and 10:1). Where higher flows do occur and scour potential is increased,
19 we propose a rock cladding. This cladding will be designed to allow limited vegetation intrusion, similar
20 to the rock facing currently in the channel. And finally, at existing and proposed bridge locations, we will
21 propose soil cement where applicable and concrete surfacing where required.

22
23 Figure 6D shows the relative risk of erosion based on velocities predicted by hydraulics models for the
24 100-year return period flowrate (please see the H&H Report). There are four (4) levels of erosion risk, as
25 follows:

- 26
27 Level 1: Level 1 is the highest level of erosion risk. These areas are the most likely to include
28 surface rock revetment or possibly concrete channel lining.
29 Level 2: Level 2 areas have reduced erosion likelihood due to lower predicted velocities. However,
30 the velocities are high enough to pose some erosion risk and the consequences of erosion
31 are relatively high. For example, the levee along Culver Boulevard is included primarily
32 because erosion impacting levee integrity may affect the roadway. In these areas, buried
33 armoring consisting of soil cement or rock revetment are considered most likely.
34 Level 3: Level 3 areas include erosion potential but the consequences of erosion are considered low.
35 For example, erosion of the north bank of the new Ballona Channel during a high flow
36 event would be a manifestation of natural processes in the restoration area, and could
37 provide ecological benefit with no damage to infrastructure.
38 Level 4: All other areas not marked are either outside the project or the erosion potential and the
39 damage risk due to the project are low. In the low risk areas within the project limits,
40 vegetation and possibly turf reinforcement (where needed) would be used.

41
42 Further analysis is required to refine the need for armoring, and its design. Discussions with the Los
43 Angeles County and US Army Corps of Engineers will inform the selected armoring approaches and

1 locations, including the use of vegetation. A more detailed discussion is included in Appendix D-2. Please
2 see the H&H Report for descriptions of predicted hydraulics.

3 4 2.3.4 Existing Levee Improvements

5 For those portions of Areas A and B where new levees will join the existing levees, ground improvements
6 will be constructed for the transition of the new proposed levees and the existing levees per the
7 Preliminary Geotechnical Design Summary (Appendix B). The transitional distance for the ground
8 improvements will be based on the mitigation of loads imposed by the new proposed levees upon the
9 existing levees.

10 11 2.3.4.1 *Levee Tie-Ins*

12 Levee tie-ins refer to the locations where new levees abut existing levees, and construction activity is
13 included in the preliminary design to develop an integrated and seamless flood control system. Tie-ins are
14 located at the upstream and downstream limits of the Area A Levee, at the upstream limit of the Culver
15 Levee and at the downstream limits of the West Area B and Interim Levees. In areas where the existing
16 Ballona Creek levees will remain long term the project geotechnical engineer provisionally recommends
17 implementation of ground improvements, such as deep soil mixing, to increase seismic stability and to
18 reduce seismic deformations. The extent of ground improvement will be revisited during final design
19 following analysis of the results of the geotechnical investigation.

20
21 In addition, the existing levee crest elevations would be raised in areas at the tie in locations..

22 23 2.3.4.2 *Ballona Creek Levees – Area A & B*

24 During construction in Area A and Area B, the project will maintain a minimum 70 feet wide offset for
25 excavations adjacent existing levees to maintain an adequate static Factor Safety during a design flood
26 event during construction. The offset will provide a stability berm against the existing levees. Excavation
27 within the offset would only occur immediately prior to breaching.

28 29 2.3.4.3 *Ballona Creek Levee - Area C and between Jefferson and Culver*

30 In the conceptual design, two areas of fill are conceptually located adjacent to existing levees. In Area C,
31 the South Area C Fill Mound is located adjacent to the existing North Ballona Creek Levee. In Area B,
32 the fill mound between Jefferson and Culver Boulevards is located adjacent to the Ballona Creek South
33 Levee.

34
35 The project is currently considering two potential approaches for these reaches of the existing levees:

- 36
37 1. Perform ground improvements along the full length of the levees as described above for the levee
38 tie-ins.
- 39 2. Construct new engineered flood control levees behind the existing Ballona Creek levees. The new
40 flood control levees would be tied into the existing Ballona Creek levees at the upstream and
41 downstream limits. The existing levees would undergo ground improvements and raised as
42 needed at the tie-ins. This approach offers some distinct advantages:

- The planned fill mounds are already above flood elevations with the required freeboard and may include a levee core within the design section.
- Incorporating a new levee core into the planned fill mounds limits the need for costly ground improvements along long reaches of existing levee adjacent to the planned fill mounds.
- Replacing the existing levees provides additional opportunities for restoration adjacent to Ballona Creek and increases flood conveyance.
- Opening the Ballona Creek section upstream of the currently planned restoration reach may help even out drops in the flood water surface profile between Centinela Avenue and Lincoln Boulevard.

2.4 BALLONA CREEK REALIGNMENT

The realigned Ballona Creek Channel is presented in Figure 7 and channel sections are presented in Figures 7A and 7B. A fully-connected Ballona Creek channel and wetland system would be restored across the site, beginning west of the Culver Bridge and extending through the site to the southwest (downstream) project boundary. The existing levees would be removed, and a more sinuous channel with two meander bends would be created through the site. The existing Ballona Creek channel would be filled between the meanders. The proposed channel alignment is designed to mimic natural channel forms and support the desired habitat, vegetation, and wildlife species. The channel alignment is also intended to avoid cultural resource areas identified by Tongva tribal representatives; however, actual locations of any cultural resources are not known.

Once constructed, the earthen channel would not be confined to a rigid alignment. Some gradual channel migration and localized erosion and sedimentation would occur. The overall channel location would be guided by the sloping restored marshplain and adjacent upland habitats. The channel alignment would only be fixed where required to protect adjacent infrastructure. In these locations, the restoration proposes some setback bank armoring (e.g. buried rock protection; see Section 2.4.3). The restored Ballona Creek banks and floodplain would experience periodic erosion and deposition, which are typical for natural river and estuary environments. The goal is to accommodate and support this level of channel and floodplain dynamics, while protecting developed areas outside the project boundaries..

2.4.1 Channel Sizing

The realigned channel is generally sized to match the existing channel dimensions, with a top width of approximately 250 feet at MHHW. Channel depths would be similar to existing depths, ranging from about 2 to 8 feet below MLLW (channel bed invert elevation of about EL -2 to -8 ft NAVD). The channel banks would be graded to slopes of approximately 5H:1V (horizontal:vertical) to provide intertidal sediment flats and low marsh habitat. On the inside of each meander bend, the channel bank has a flatter slope to create a channel bar or bench typical of natural river systems to add to habitat complexity. The bench extends at a 20H:1V slope from EL 4.5 ft. to EL 0.5 ft. This bench results in a low flow channel that is about 60 feet narrower (at EL 0.5 ft) than the existing channel. ESA PWA identified the San Elijo Lagoon/Escondido Creek channel in Del Mar, CA as a reference site for the channel design and cross-section. Additional reference data and channel cross-section refinements will be considered in subsequent design phases.

1 ESA PWA analyzed potential equilibrium channel dimensions for typical fluvial and tidal flows using
2 empirical hydraulic geometry relationships (see H&H Report Section 6). This assessment indicates that
3 the existing and proposed channel dimensions are somewhat larger than the predicted equilibrium channel
4 dimensions; however, the predicted equilibrium dimensions assume adequate sediment supply, Ballona
5 Creek is a sediment-supply limited system, and channel dimensions may therefore never fill in to
6 equilibrium dimensions. A smaller channel size closer to equilibrium dimensions may be considered in
7 subsequent design refinement (see H&H Report Section 6).

8 9 2.4.2 Sinuosity

10 The realigned channel sinuosity (ratio of channel length to distance between channel endpoints) is 1.2,
11 which is comparable to the sinuosity of other natural Southern California creek and tidal wetland systems
12 (i.e., natural existing and historic systems).

13 14 2.4.3 Armoring

15 The project anticipates that meanders will be constructed by filling the channel with rock dikes to form
16 the channel crossings and buttress fill placed between them. The dikes would be created with a rock
17 gradation that includes a wide range of sizes to limit migration of sediment between the voids. Between
18 the upstream and downstream rock dikes, the existing channel would be filled with earth to form the
19 channel crossings.

20
21 Following construction, the rock dikes would be left in place to help armor the channel meander bends.
22 Larger rock will be placed as an overlay on the rock dikes to armor against high velocity and turbulence
23 induced scour. During final design, the project will determine the height and width of these rock dikes to
24 provide adequate armor at the channel meanders.

25 26 2.4.4 Berms and Islands

27 Berms and islands are included adjacent to the realigned Ballona Creek channel at the top of bank of the
28 channel. These features are intended to mimic the low berms that form adjacent to natural tidal channels
29 as coarser sediment drops out of suspension where overbank flows leave the channel. These features are
30 also intended to divide the main Ballona Creek corridor from adjacent marsh drainage basins to support
31 larger (higher order) tributary tidal channel networks within the marsh (see Section 2.5.3). In addition,
32 these features help guide more frequent flood flows to overbank areas away from the flood control levees
33 and away from the existing straight Ballona Creek alignment.

34
35 Islands are larger features located on the inside of the first two meander bends. In the preliminary grading
36 plans, the islands extend up to EL 8.0 ft and would support high marsh and transition zone plants. These
37 islands would provide refuge during high tides and moderate storm flows and provide an area for wildlife
38 away from predators, humans, and pets.

39
40 Berms are lower features located along the channel extending up to EL 6.5 ft. The berms help to
41 concentrate flows into the higher order tidal drainage channel networks that convey tidal exchange into
42 the marsh basins adjacent to the larger Ballona Creek channel. The berms would support mid and high
43 marsh plants and provide high tide refuge for wildlife.

1 2.4.5 Levee Breaching and Lowering

2 The existing Ballona Creek levee would be lowered to match grades as shown on the grading plans. At
3 locations where the new Ballona Creek alignment crosses the existing levee, the existing levee would be
4 breached to the full width and depth of the planned Ballona Creek section taking into account the oblique
5 angle of the crossing. The existing concrete and rock armoring would be removed. Concrete armor may
6 be recycled for use on site.

7
8 2.5 AREA A – TIDAL WETLAND, TRANSITION ZONE, AND UPLAND RESTORATION

9
10 The existing elevations in Area A, which range from about EL 10 to 23 ft NAVD, are 5 to 18 ft above
11 present-day wetland elevations due to the placement of dredged material during the construction of
12 Marina del Rey harbor, the Ballona Creek channel, and other facilities. The restoration proposes to
13 excavate and grade Area A to restore marsh, transition zone, and upland habitats as shown in Figure 8.
14 The restoration would create a long gently-sloping transition from upland habitats along the northern
15 perimeter of Area A down to vegetated marsh habitat and mudflat habitat adjacent to the restored Ballona
16 Creek channel. The preliminary design includes two options for treating the gas wells in west Area A for
17 the Interim Build Out. Option A (Figure 5A) will be implemented if the gas wells are not removed prior
18 to the Interim Build Out. In Option A, the gas wells will remain and be protected in place and the area
19 around the wells will not be excavated. In Option B (Figures 5B), the wells will be removed and the area
20 around the wells will be excavated to create restored wetland, transition zone, and upland habitat. In the
21 Full Build Out (Figure 5C), the Area A wells will be removed as in Option B. Preliminary design sections
22 for the Full Build Out are presented in Figure 8A.

23
24 The broad transitional slopes between wetland and upland habitats are intended to increase the resiliency
25 of the restored wetlands to future sea-level rise. These gradual slopes would allow wetland habitats to
26 transgress up slope with rising sea levels through the conversion of upland transition habitats to wetland
27 habitats. This process of “coastal rollover” has occurred over geologic time, and is expected to continue
28 and accelerate with projected sea level rise. The H&H Report (Section 6) includes an assessment and
29 figures showing estimated habitat projections for future sea-level rise scenarios.

30
31 Table 3 lists habitat elevations used for the Preliminary Design of restored habitats in Area A and B.
32

1 **Table 3 Habitat elevations.**

<u>Habitat elevations</u>		<u>Elevation</u>		<u>Note</u>
<u>Bottom of:</u>	<u>Top of:</u>	<u>ft MLLW</u>	<u>ft NAVD</u>	
Upland	Transition Zone	9.8	9.6	9.8 ft MLLW per Zedler (2001)
Transition Zone	High Marsh	7.5	7.3	7.5 ft MLLW per Zedler (2001), 0.3 ft below highest observed tide level
High Marsh	Mid Marsh	6.5	6.3	1 ft above MHHW, consistent with San Dieguito / Josselyn and Whelchel (1999); exceeded by spring tides
Mid Marsh	Low Marsh	4.8	4.6	MHW, similar to (0.2 ft lower than) San Dieguito / Josselyn and Whelchel (1999)
Low Marsh	Mudflat	3.8	3.6	1 ft above MTL, similar to San Dieguito / Josselyn and Whelchel (1999)
Mudflat	Subtidal - Small Subtidal Channel	0.0	-0.2	MLLW
Subtidal - Small Subtidal Channel	Subtidal - Large Subtidal Channel	-2.8	-3.0	

2

3 2.5.1 Tidal Marsh

4 Preliminary grading plans for the Area A tidal marsh are presented on Figure 8 and design sections are
 5 presented on Figure 8A. The Area A restored tidal marshplain will range in elevation from low marsh (EL
 6 4.5 ft NAVD) at the channel bank up to high marsh (EL 7.3 ft NAVD) at the upland transition zone (see
 7 habitat elevations in Table 3). Marshplain slopes will range from about 100H:1V to 150H:1V.

8

9 The marshplain will be graded to slope and drain towards two networks of tributary tidal channels (see
 10 Section 2.7.1) extending from the outside of the Area A channel meander bend. This grading will form
 11 two marsh “drainage basins,” one in east Area A and one in west Area A. These marsh drainage basins
 12 will encourage the restoration of larger (higher order) tidal channel systems and associated habitat
 13 complexity. The eastern marsh channel basin is also intended to convey Ballona Creek overbank flows
 14 during storm events.

15

16 WRA’s CHRAMP (Comprehensive Habitat Restoration and Adaptive Management Plan) describes the
 17 tidal marsh revegetation plan. For the purposes of this PDR, we assume the following tidal marsh
 18 revegetation approach:

19

- 20 • Introduction of cordgrass to establish low marsh vegetation.
- 21 • Rely on natural recruitment of pickleweed and other salt marsh vegetation in mid marsh areas
 22 between EL 4.5 ft and EL 6.3 to 6.5 ft NAVD.
- 23 • Planting of pickleweed and other salt marsh vegetation in high marsh areas between EL 6.3 to 6.5
 24 ft NAVD and EL 7.3 ft NAVD since natural recruitment in this high marsh zone is expected to
 25 take many years.

26

1 2.5.2 Salt Pans

2 Salt pans will be created by excavating by excavating 0.5 to 1 foot depressions around the perimeter of
3 Area A tidal marsh that are intended to allow infrequent tidal inundation during spring high tides, shallow
4 ponding, evaporation, high soil salinity (e.g., salt crust formation), and decreased vegetation
5 establishment. Salt pan habitat will be created along the edge of the high marsh and transition zone
6 habitats in wider high marsh areas between channels (Figures 4, 5A - 5C; note salt pans are not currently
7 show on grading plans). Salt pan depressions will be over-excavated by 1 to 2 feet and back-filled with
8 compacted clay material to encourage ponding. Sill elevations will be between EL 5.5 and 6.5 ft NAVD
9 to provide the appropriate frequency of tidal inundation.

10
11 With future sea-level rise, salt pans are expected to eventually become vegetated marsh as they are
12 increasingly inundated. Restored seasonal wetlands (Section 2.5.4) are intended to provide future salt pan
13 habitat with sea-level rise.

14
15 2.5.3 Transition Zone and Upland

16 Preliminary grading plans for the Area A transitional Zone and Upland are presented on Figure 8 and
17 design sections are presented on Figure 8A. Transition zone and upland habitats will be restored around
18 the perimeter of Area A. This wetland-upland transition zone is intended to provide ecotone habitat and
19 provide areas for marsh transgression with projected future sea-level rise. Undulating transition and
20 upland habitat areas will be graded, with shallower slopes of 80H:1V to 100H:1V forming peninsulas and
21 steeper slopes of up to 40H:1V forming coves. The flatter peninsulas will provide areas for salt pans and
22 the coves will provide tidal marsh drainage areas for smaller tidal channels. Higher upland mounds
23 (shown as idealized land forms at EL 20 feet in Figures 5A - 5C) will provide irregular upland topography
24 and the opportunity to restore dune habitat.

25
26 Transition zone habitats will be between EL 7.3 to 9.6 ft NAVD and upland habitats will be above EL 9.6
27 ft NAVD per Table 3. WRA's CHRAMP describes the transition zone and upland revegetation plan. For
28 the purposes of this PDR, we assume these areas will be planted and irrigated/maintained as appropriate.

29
30 2.5.4 Seasonal Wetlands

31 Seasonal wetlands will be created by excavating by excavating 0.5 to 1 foot depressions in upland areas
32 around the perimeter of Area A that are intended to capture and pond runoff from upland areas. Seasonal
33 wetlands may be created in marsh/upland coves as shown in Figures 4, 5A - 5C (note seasonal wetlands
34 are not currently show on grading plans). Seasonal wetland depressions will be over-excavated by 1 to 2
35 feet and back-filled with compacted select material to encourage ponding. Seasonal wetland sill
36 elevations will be between EL 7.0 and 8.0 ft NAVD. The design will include a variety of seasonal
37 wetland depths and sill elevations to provide a range of hydrology (e.g., as in the Hamilton Army Airfield
38 Wetland Restoration design by PWA (Dec 2008))

39
40 With future sea-level rise, seasonal wetlands are expected to eventually become tidally inundated. The
41 seasonal wetlands are intended to provide future salt pan habitat with sea-level rise.

1 2.6 AREA B – TIDAL WETLAND, TRANSITION ZONE, AND UPLAND RESTORATION

2
3 Restoration of Area B includes:

- 4
- 5 1. North Area B full tidal wetland restoration between the new Culver levee and the realigned
 - 6 Ballona Creek channel (Section 2.6.1)
 - 7 2. West Area B full tidal wetland restoration of the existing West Area B managed muted marsh in
 - 8 the final phase of the Project (Section 2.6.2)
 - 9 3. South and East Area B managed wetland restoration inboard (behind) the Culver levee (Section
 - 10 2.6.3).

11
12 2.6.1 North Area B – Tidal Wetland, Transition Zone, and Upland

13 Preliminary grading plans for the North Area B tidal wetland, transitional zone and upland are presented

14 on Figure 8 and design sections are presented on Figure 8A.

15
16 Tidal marsh will be restored between the new Culver Levee and the realigned portion of Ballona Creek in

17 north Area B, with a full tidal connection between the wetlands and Ballona Creek. Existing elevations in

18 north Area B range from about EL 6 to 9 ft NAVD. The higher areas are filled above current marsh

19 habitat elevations. North Area B will be graded to create a marshplain drainage basin between the

20 realigned channel and the new levee, with elevations from 4.5' NAVD to 6.5' NAVD. The marshplain

21 basin would slope towards a tidal channel system that drains downstream to the outside bend of the Area

22 B channel meander. The marshplain basin and channel system are also intended to convey Ballona Creek

23 overbank flows during storm events. A gently sloping transition zone and upland habitats will be created

24 between the marshplain and the new levee, which may include dunes and a small upland peninsula at the

25 curve in the Culver Levee as shown in Figures 4, 5A - 5C.

26
27 2.6.2 West Area B – Tidal Wetland, Transition Zone, and Upland

28 In the Interim Phase of the Project (after Phase 1 and 2; see Section 1.6), the majority of the existing

29 managed marsh in West Area B will be maintained and managed as is. In the final phase of the Project,

30 West Area B will be restored to full tidal wetland by removing the existing tide gate, creating an open

31 tidal channel by breaching the existing Ballona Creek levee, and removing/ lowering the Ballona Creek

32 levee. Implementation of the final phase will proceed within an adaptive management plan (see WRA's

33 CHRAMP). A component of the adaptive management plan is to successfully restore habitats in other

34 areas of the site in Interim Phase to minimize potential impacts of West Area B full tidal restoration.

35
36 2.6.2.1 *Interim Phase*

37 A new levee will be constructed between the Culver levee and the existing West Area B levee to protect

38 West Area B during the Interim Phase. This levee section will be removed for the Full Build Out and is

39 therefore referred to as a temporary Interim Levee.

40
41 The new West Area B perimeter levee will be constructed in the Interim Phase in anticipation of the final

42 phase of the project below (see Section 2.3.2.3). Transition zone and upland habitats will be restored on a

43 gently-graded undulating slope (approximately 10 to 20H:1V) between the existing managed wetlands

1 and new levee. These restored habitats may include dunes and shallow depressions to function as small
2 salt pans under full tidal conditions in the Final Phase of the Project (as shown in Figures 4 and 5C).

3 4 2.6.2.2 *Final Phase*

5 In the Final Phase of the Project or Full Build Out, West Area B will be restored to full tidal wetland by
6 removing the existing tide gate, creating an open tidal channel by breaching the existing Ballona Creek
7 levee, lowering the Ballona Creek levee, and removing a portion of the Interim levee. The open tidal
8 channel would provide a full range of tides and creek water levels in west Area B. The existing levee
9 would be lowered to about EL 5 ft NAVD to restore mid marsh habitat. The existing system of channels
10 in the managed marsh may be enhanced by excavating new channels as shown in Figure 9. The
11 preliminary design for the levee breach and tidal channels is discussed in Section 2.7.

12
13 The Interim levee will be dismantled, with the material moved to create the upland West Habitat
14 Peninsula, roughly in the same location. This action would take place after the Gas Company's wells are
15 decommissioned (see discussion in Section 2.10.1). If the gas wells are not removed prior to the Full
16 Build Out, the Interim Levee will be reconfigured and extended around the gas wells to provide flood
17 protection, and a stormwater drainage culvert will be installed in the levee to maintain storm drainage for
18 the gas well area enclosed by the levees.

19
20 The upland habitat peninsula as shown in Figures 4, 5A - 5C is intended to:

- 21
22 1. Provide larger areas of upland habitat and high tide refuge for wildlife along the south side of the
23 channel.
- 24 2. Guide and re-converge Ballona Creek storm flows through the realigned Ballona Creek channel
25 back into the existing channel alignment downstream in the Final Phase.
- 26 3. Beneficially re-use soil excavated to restore wetlands in Area A in the Interim Phase.

27
28 The West Area B managed marsh is at elevations that are expected to support mudflat, low marsh and
29 mid marsh habitat after full tidal restoration. These areas will therefore remain at existing grade (without
30 grading to raise or lower the marshplain). A large portion of the existing pickleweed vegetation in this
31 area is at elevations that would support mudflat and low marsh under full tidal conditions. The
32 pickleweed is not expected to persist at low marsh elevations; however, mid marsh channel berms may be
33 created when tidal channels are excavated as described in Section 2.7.

34
35 WRA's CHRAMP includes a revegetation plan. For the purposes of this PDR, we assume that cordgrass
36 will be introduced to West Area B to establish vegetated low marsh habitat. In the absence of cordgrass,
37 West Area B is expected to convert to mudflat habitat over time.

38 39 2.6.3 South and East Area B – Managed Wetland Restoration and Enhancement

40 Inboard or behind the new Culver Levee, the following wetland areas will be restored:

- 1 1. South Area B: the existing muted tidal managed wetland south of Culver Blvd. and west of the
2 Gas Company road (referred to as South Area B) would be retained and enhanced by restoring
3 tidal channels.
- 4 2. East Area B: the existing non-tidal pickleweed seasonal wetland south of Jefferson Blvd. and east
5 of the Gas Company road (East Area B) would be restored to managed tidal wetland by providing
6 a new tidal connection and excavation of tidal channels.

7
8 The existing areas of pickleweed and other mid marsh plants in South and East Area B are at the
9 appropriate tidal elevation to persist as mid marsh habitat after restoration. In South and East Area B,
10 sinuous and branching tidal channel networks will be excavated through the marsh habitats (see Section
11 2.7.3 and 2.7.4). These tidal channel systems would connect to the restored Ballona Creek channel to
12 create tributary tidal channel networks.

13
14 Water levels in the South and East Area B managed wetlands will be controlled by two new water control
15 structures at the locations shown in Figures 5A - 5C (see Section 2.8.1 for more details). The water
16 control structures will provide tidal inundation up to an elevation acceptable for flood management and
17 storm drainage, but will close during larger storm events in Ballona Creek to limit high water levels in
18 South and East Area B (see Section 1.2). The managed wetlands and water control structures will be
19 designed to protect Culver Blvd., the Gas Company facilities, and areas draining to the FWM from
20 flooding during the design storm event (LA County capital flood). Note that the FWM was designed to
21 overflow into East, South, West, and North Area B. The FWM was designed assuming managed tidal
22 wetland restoration in Area B, with an average managed high tide level near mean higher high water (EL
23 5.2 ft NAVD, Psomas 1999). In this scenario, Psomas (1999) showed that Culver Blvd. and the Gas
24 Company would not be flooded in the design storm event.

25
26 The existing levee between the FWM and East Area B is above the elevation of normal ocean high tides
27 and would be maintained as is.

28
29 In subsequent phases of the design, South and East Area B flood scenarios and water levels will be
30 analyzed. Appendix H includes calculated rainfall-runoff hydrology for areas draining to East and South
31 Area B. Hydraulic analyses will be performed to design the South and East Area B water control
32 structures and assess water levels for flood conditions.

33
34 If needed, a berm may be constructed in East Area B between Culver Blvd. and the managed wetlands to
35 protect the low point in Culver Blvd. from flooding. Additional berms may be constructed around the
36 perimeter of East and South Area B to protect Gas Company facilities if needed. These berms are not
37 currently included in the preliminary grading plans.

38
39 The design will consider and allow for South and East Area B wetland management options, which may
40 include:

- 41
42 • Muted managed tidal inundation

- Brackish marsh management, primarily in East Area B, supported by freshwater discharge from the FWM
- Seasonally-closed wetland habitat similar to historic 1850s wetland habitats at Ballona, in which the water control structures would be closed to limit tidal circulation and create ponded/evaporative conditions
- Salt pan habitat creation
- Future management options with projected sea-level rise.

These management options will be assessed further in subsequent phases and the South and East Area B water control structure and tidal channel designs will be refined to accommodate the preferred set of management options. Water control structures, including the FWM structures, are discussed in Section 2.8. Tidal channels are discussed in Section 2.7.

2.7 TIDAL CHANNELS

Networks of branching, sinuous tidal channels will be excavated in the restored wetlands. The tidal channel networks will extend from and drain to Ballona Creek. The purpose of the tidal channels is to convey tidal flows and sediment to the restored wetlands, providing tidal circulation (inundation and drainage) to support wetland vegetation and functions.

The tidal channel planform layout (e.g., channel length per marsh area and sinuosity) and sizing (cross-section dimensions) are based on empirical tidal channel layout/sizing data from reference wetlands (tidal channel hydraulic geometry relationships; PWA 1995 and Williams and others 2002). The larger (higher order) tidal channels branch (bifurcate) into smaller (lower order) channels. The largest channel systems are fifth order, meaning the channels branch into smaller channels five times (ending in the smallest or first order channels). The Preliminary Design assumes excavation of the full channel network, including first order channels, because complete tidal channel networks are not expected to form naturally after restoration. The intent is to restore larger (higher order) channel systems to create a greater range of channel habitats and habitat complexity. The larger channel systems are generally laid out to drain to the outside bends of the realigned Ballona Creek channel as in natural wetland systems.

Figure 9 shows the preliminary tidal channel layout by channel order. The smaller channels (second order and the smallest/first order channels) are not shown in Figure 9, except for smaller channels draining directly to Ballona Creek. Tidal channels are not currently shown in the preliminary grading plans. Table 4 lists preliminary tidal channel dimensions by channel order. Area A and B tidal channel networks are discussed in the sections below.

1 **Table 4 Tidal Channel Dimensions by Channel Order.**

Channel order	Top width at MHHW (ft)	Bottom width (ft)	Side slope (H:V)	Invert elevation (ft NAVD)	Depth (ft below MHHW)	Depth (ft below MLLW)	Note
5	80	10	5	-1.8	7	1.6	Subtidal
4	35	5	3	0.2	5	-0.4	Subtidal/intertidal
3	20	4	2	1.2	4	-1.4	Intertidal
2	10	4	1	2.2	3	-2.4	Intertidal
1	7	3	1	3.2	2	-3.4	Intertidal

2 Note: Channels are ordered from smallest (first order) to largest. Two first order channels join to form a second
 3 order channel, two second order channels join to form a third order channel, etc.

4
 5 Within existing marsh areas in West, South, and East Area B, material excavated to construct tidal
 6 channels will likely be placed adjacent to the excavated channels (sidecast) to form higher marsh channel
 7 berms adjacent to the channels. These berms would be a few feet high, depending on the elevation of the
 8 adjacent wetland. This approach creates channel berms and higher marsh habitat that are found in natural
 9 marsh systems and provides an efficient method for handling excavated material while limiting impacts to
 10 existing marsh areas.

11
 12 **2.7.1 Area A**

13 Two large (fourth order) channel systems will be restored in Area A (see Figures 9, 5A - 5C, and Table
 14 4). These channel systems will connect to the outside of the Area A meander bend and will extend into
 15 the Area A marsh areas to the east and west. The ends of the channel systems will drain the marsh coves
 16 (see Section 2.5). The east Area A channel system will also convey Ballona Creek overbank storm flows
 17 through the restored marsh floodplain and back into Ballona Creek. Channel berms along the realigned
 18 Ballona Creek will define the marsh drainage areas and outlets for the Area A tidal channel systems (see
 19 Section 2.4.4).

20
 21 One smaller (second order) channel system will be restored at the west end of Area B as shown in Figures
 22 9, 5A - 5C. This channel may also convey some overbank storm flow.

23
 24 **2.7.2 North Area B**

25 A large (fourth order) channel system will be excavated in the restored marsh area between the realigned
 26 Ballona Creek channel and the Culver Levee (see Figures 9, 5A - 5C and Table 4). This channel system is
 27 intended to convey overbank storm flows. The Ballona Creek berm at the upstream end of this channel
 28 system (along the outside of the first Ballona Creek meander bend) will be armored to reduce the
 29 potential for scour and channel avulsion (see Section 2.4.3).

30
 31 The East Area B tidal channel system (fifth order) will continue through a water control structure (see
 32 Section 2.8.1) connected to the North Area B channel system to connect to Ballona Creek. Smaller
 33 channels will drain the restored marsh to the west (e.g., first order channels shown in Figures 9, 5A - 5C).

1 2.7.3 East Area B

2 The Preliminary Design includes excavation of a large (fifth order) channel system in the East Area B
3 restored managed marsh. This channel system would connect to Ballona Creek through a new water
4 control structure (see Section 2.8.1) and North Area B. The intent of this channel system is to convey tidal
5 flows and provide tidal inundation throughout the managed marsh. Different East Area B management
6 options will be considered and allowed for in the final design (see Section 2.6.3). The East Area B
7 channel design will be refined to accommodate the preferred management options. These refinements
8 may include:

- 9
- 10 • Extending larger channels to the FWM outflow locations to convey freshwater discharges and
11 encourage brackish marsh development. The FWM outflow structures to East Area B are
12 discussed in Section 2.8.2.
 - 13 • Excavating fewer channels if consistent with certain management options
 - 14 • Connecting the East Area B and South Area B channel systems through the water control
15 structure in the Gas Company Road (e.g., a new structure or an improvement of the existing
16 culver; see Section 2.8.3).

17

18 Note that the main East Area B tidal channel will cross the existing gas pipeline in this area (see Figure
19 3). A section of the gas pipeline may be replaced to run under the channel as described in Section 2.10.40.
20 No other channels will be excavated across the pipeline to preserve access to the pipeline from the south
21 and north.

22

23 2.7.4 South Area B

24 The Preliminary Design includes excavation of a large (fifth order) channel system to enhance the South
25 Area B managed marsh. The channel system would connect to West Area B through a new water control
26 structure (see Section 2.8.1). The channel design may be refined to accommodate different marsh
27 management options (see Section 2.7.3 and 2.6.3).

28

29 2.7.5 West Area B

30 The Preliminary Design includes excavation of a large (fifth order) channel system in West Area B in the
31 Final Phase of the Project. The Interim Phase of the Project will likely only include channel excavation to
32 connect the West and South Area B channel systems through the new water control structure. The main
33 channel and levee breach to Ballona Creek will have similar dimensions to the fifth order channel
34 dimensions listed in Table 4.

35

36 The West Area B tidal channel design will be refined based on further consideration of restored West
37 Area B low marsh and mudflat habitat conditions and functions. These refinements may include less
38 channel excavation.

1 2.8 HYDRAULIC STRUCTURES

2
3 2.8.1 Culver Levee Water Control Structures

4 Two new water control structures will be installed in the new Culver Levee and across Culver Boulevard
5 and Jefferson Boulevard:

- 6
7 1. For the South Area B managed wetland enhancement, a bank of culverts with gates will be
8 installed in the new Culver levee and under Culver Blvd. between South and West Area B.
9 2. For the East Area B managed wetland restoration, a second bank of culverts with gates would be
10 installed in the new Culver Levee and under the intersection of Culver Blvd. and Jefferson Blvd.
11 to restore a tidal connection between east Area B and Ballona Creek.
12

13 The proposed water control structure locations are shown in Figures 5A - 5C.

14
15 These culverts will be sized as a minimum to convey the 100-year storm events for the local area flows
16 out to Ballona Creek. The size may be increased to allow tidal action. The structures will be box culverts
17 within the roadways as there are utilities that must be crossed that in one case (A City of Los Angeles 230
18 kV electrical line) would be difficult to relocate. Before and after the roadway, the conduits may be
19 transitioned to a series of pipes to allow installation of traditional flap gates for protection against Ballona
20 Creek flows, and to allow managed tidal circulation. There are three conduits crossings for flows
21 generated from south of Area B. From east to west, the conduits must convey approximately 230 cfs for
22 East Area B, 160 cfs for South Area B, and 180 cfs for the existing Pershing Drain between Jefferson and
23 Culver Blvds. Assuming an available head of 2.0 feet, the flow rates will require conduits with cross
24 sectional areas of approximately 50 s.f., 37 s.f., and 34 s.f. respectively (from east to west). These
25 numbers assume a conduit length of approximately 300' for the east and middle conduits to allow
26 sufficient length to cross the roadway and proposed levee, and 150' to get to the parking lot detention
27 area.
28

29 Each of the two banks of culverts with gates in the Culver levee would each consist of multiple culverts
30 and gates (e.g., six 5-foot diameter culverts with gates). The gates will be designed to close or limit inflow
31 during certain storm events in Ballona Creek to limit high water levels in South and East Area B (e.g.,
32 self-regulating tide gates or gated culverts that provide only limited inflow and the required outflow
33 capacity). Appendix H includes additional discussion of water control structures.
34

35 The existing drainage culvert under the Gas Company Rd. between South and East Area B will be
36 modified (e.g., by expanding the culvert and/or installing gates). The modified culvert will be used to
37 manage the connection between South and East Area B (e.g., for wetland habitat management,
38 stormwater management, and to maintain circulation while other water control structures are
39 maintained).
40

41 2.8.2 Freshwater Marsh Water Control Structures

42 The existing FWM is situated at the easterly edge of Area B, south of Jefferson Boulevard. The FWM
43 serves multiple functions including acting as the downstream end of a stormwater conveyance system,

1 providing attenuation of upstream storm flow volume and flow rate, providing water quality treatment of
2 urban inflow, and providing freshwater habitat.

3
4 There are a number of key functional elements of the FWM that will be maintained as is or adjusted with
5 the project. These include:

- 6
7 1. Existing habitat areas within the perimeter berm of the FWM will remain undisturbed.
- 8 2. The existing overflow weir into the Brackish Marsh area will be maintained as is relative to
9 location. A design feature of the overflow weir is the ability to adjust the overflow elevation. The
10 overflow weir will be modified to raise the overtopping elevation as needed to provide
11 appropriate flood protection with sea level rise, and to provide necessary storage volume for the
12 overflows.
- 13 3. Until the existing levees are removed, the existing outflow pipe to the Ballona Channel must be
14 maintained to provide regular outflow to maintain circulation from the FWM for water quality
15 purposes. After levee removal, connection of this outlet will be relocated through the new levee
16 to provide final overflow for larger storm events, and may also be modified to route into the
17 Brackish Marsh area through an existing supplemental overflow pipe in Jefferson Boulevard.
18 There is also a small existing overflow pipe at the south end of the FWM that has a valve
19 structure currently closed. These outflows must be maintained for minor, non-storm flows, to
20 maintain circulation.
- 21 4. The FWM storm flows cannot be routed in their entirety to the Brackish Marsh since the available
22 storage volume to contain up to the 100-year storm within the project area south of Jefferson and
23 Culver Boulevards is insufficient to eliminate flooding of low-lying, upstream properties. Further
24 analysis is required to ascertain the effects of sea level rise on the available storage, and whether
25 increased tidal range can be accommodated (see additional discussion in Section 2.6.3).

26
27 There are three water control outlet structures from the FWM. The existing northerly outlet drain from the
28 FWM is a multi-stage conduit, depending on its location. The main conduit is a 10 feet wide by 6 feet tall
29 reinforced concrete box. Where it crosses Jefferson and Culver Boulevards, it is transitioned to a double,
30 10 feet wide by 3 feet tall reinforced concrete box. This allows the same cross sectional area in half the
31 height. At the connection to the Ballona Creek, the conduit transitions to a triple 5 feet diameter
32 reinforced concrete pipe (RCP). The triple 5 feet dia. pipes connect to the Ballona Creek with flap gates to
33 eliminate backwater into the FWM from the Creek. With the project, this pipe will substantially remain in
34 place. The most northerly portion will be reconfigured to meet the proposed levee location with the same
35 concept of triple 5 feet diameter RCP's and flap gates. At the south end of this conduit is a specially
36 designed weir allowing elevation adjustments from approximately EL -0.3 ft to 7.3 ft NAVD. This wide
37 range allows full dewatering of the FWM for maintenance if that is ever necessary. This internal weir
38 structure controls the water surface elevation in the FWM and will remain as is.

39
40 The next structure is an overflow weir directing overflow from upstream storm events into East Area B.
41 This weir design allows for some adjustment in elevation. Its lowest and currently set elevation is
42 approximately EL 7.0 ft NAVD. Its highest setting is at an elevation of 9.25 ft NAVD. With additional
43 structural modification, it is possible to set the elevation as high as approximately 10.0 ft NAVD before

1 causing upstream drainage impacts. At its current crest elevation of 7.0 ft NAVD, and with closure of the
2 flap gate with Ballona Creek flows, overtopping into the Brackish Marsh occurs for storms over
3 approximately the one-year storm. Depending on the desires of the project, and with concurrence of the
4 organization responsible for maintenance of the FWM, the weir structure elevation could be adjusted to
5 the elevation range between 7.0 ft and 10.0 ft NAVD.

6
7 The final water control structure is a 24-inch diameter pipe stub out toward the south end of the FWM.
8 This pipe was installed for multiple functions – as an alternate drain location for dewatering of the FWM
9 for maintenance, for water quality circulation if needed within the FWM, and for “freshening” of brackish
10 marsh in East Area B if needed. This pipe has a valve assembly that is currently closed. A drainage
11 channel may be required to extend from a tidal channel in East Area B to the end of this pipe that would
12 allow it to be opened if desired.

13 14 2.8.3 Culver Boulevard Stormwater Management

15 Stormwater drainage for the west end of Culver Boulevard will be managed as described below. In
16 addition, a drainage swale will be created in the area between the new Culver Levee and Culver
17 Boulevard. Culver Boulevard stormwater management features are shown in Appendix H.

18 19 2.8.3.1 *Existing Conditions*

20 At the southwest corner of Area B is a developed commercial area fronting Culver Boulevard. This
21 development is at a very low elevation in some cases below 6.0 ft NAVD. This is a low point of Culver
22 Boulevard and has historically had flooding problems at, and adjacent to, the intersection of Culver
23 Boulevard and Nicholson. There are a number of storm drains in the area with the primary collection
24 drain for flows from the Westchester Bluffs area conveyed westerly of the intersection toward the ocean.
25 This drain is under sized for larger storm flow events. This was recognized and an overflow drain in
26 Nicholson exists to convey the excess overflow to the north outletting on the north side of Culver
27 Boulevard at the intersection. There is a small ditch that routes this overflow runoff into Area B to one of
28 the small tidally influenced ditches in the area. Due to tidal action, the capacity of this overflow ditch and
29 the surrounding area that is available for storm water storage is sometimes exceeded causing flooding of
30 Culver and a few of the adjacent properties.

31 32 2.8.3.2 *Proposed Drainage Conditions*

33 With the construction of the proposed levees, tidal influence in this area will be eliminated. However
34 storage volume for the excess overflow drainage will also be eliminated. Therefore, replacement storm
35 water storage volume will be provided by creating a low area to approximately elevation 4.0 ft NAVD
36 between the commercial properties and the proposed levee. This storage basin will be sized to
37 accommodate the overflow volume as well as the local drainage in the area. A public storm drain pipe
38 from a downstream drain system can be extended to dewater this area if desired, or storage volume could
39 be provided to fully contain the overflow. This basin will also function as a water quality treatment
40 measure to address the minor increase in pollutant load from the proposed paved fire access road behind
41 the commercial properties, as well as a portion of the runoff from the existing paved area of Culver
42 Boulevard. Other areas of Culver Boulevard further east will drain to a shallow roadway shoulder ditch

1 provided to keep stormwater runoff away from the paved area, as well as provide an infiltration and
2 treatment function for the roadway.

3 4 2.9 AREA B AND C UPLAND FILL PLACEMENT AND HABITAT RESTORATION

5
6 The soils that are to be transported to uplands areas within Areas B and C fall into four categories:

- 7
- 8 • structural,
- 9 • non-structural,
- 10 • contaminated (non-hazardous), and
- 11 • stockpile.
- 12

13 For the proposed bike path and parking lot within Area B, soils will be placed in a structural manner to
14 reduce settlement issues of these pavement areas. Soils in other areas throughout Areas B and C will be
15 placed with a modest level of compaction that will not be considered structural fill. This will allow
16 efficient and relatively uniform compaction (although some wet soils in the later stages may have almost
17 no compaction), while still providing ability for plant and habitat establishment. Any marginally
18 impacted, non-hazardous soils would be placed in Areas B and C and covered with a minimum of three
19 feet of clean cover (Upland Cover). Soils classified as hazardous, will be offhauled and properly disposed
20 of according to state and federal regulations. And finally some soils will be required to be stockpiled for
21 subsequent phases or for removal off-site for disposal.

22
23 It is expected that short term stockpiling operations will occur throughout the project at various times. But
24 that stockpiling necessary for non-contiguous construction phasing, or stockpiling needs that would span
25 a rainy season would likely be located in the Area B upland fill area to minimize impacts to other grading
26 operations and provide the shortest distances for the multiple movements that will be necessary.

27
28 It is expected that the uplands areas have the capacity to allow adjustment in the final earthwork volumes
29 moved. As with all grading operations, volumes can be quite variable and are based on many factors. If
30 we end up with less soils volume for these areas, the grades can be lowered. And if we have more soils
31 than expected, grades can be raised. When all major grading operations are completed, the uplands areas
32 will be given a final surface contouring into their ultimate configuration. The goal will be to provide as
33 natural an appearance as possible with variations ranging from flat areas, mounds, slopes, depressions,
34 etc.

35
36 Once grading is complete, the areas will be revegetated to restore upland habitat. WRA's CHRAMP
37 includes a revegetation plan

38 39 2.9.1 Area B – Upland Fill

40 In the existing area of upland and seasonal wetland between Culver Blvd., Jefferson Blvd., and Lincoln
41 Blvd., soil excavated to restore wetlands in Area A will be placed and upland habitats will be restored.
42 Preliminary grading plans for this fill placement area are shown on Figure 10. Drainage will be contoured
43 into this fill area generally from north to south and east to west. An existing drainage inlet will be

1 adjusted to the final grade. This area may also be graded so that rainfall flows into and supports seasonal
2 wetlands and other upland habitats. A bike path and walking trail will be extended off the proposed bridge
3 across the Ballona Creek and then routed toward the easterly edge connecting to the intersection of
4 Lincoln and Jefferson Boulevards. Elevations will vary as ultimately determined by the soil volumes
5 necessary, but are expected to range from 15 to 35 feet, or from a few feet to twenty plus feet above
6 adjacent street level. Grades are currently from five to fifteen feet below street level.

7
8 If the excess soil volume is less and soil placement in Area B is not needed (e.g., if another entity agrees
9 to accept and transport the excess soil material off-site by), then this portion of Area B could be restored
10 to managed wetland as an option within the Project design.

11 2.9.2 Area C – Upland Fill

12 The preliminary grading plans for Area C North and South are presented in Figure 11.

13 2.9.2.1 *Area C North*

14
15 In Area C North, excess fill from the restoration of Area A will be placed to create upland habitats with
16 varying topography and elevations. Fill in Area C North will be contoured so that drainage generally
17 flows towards the central portions of site to the existing Fiji Ditch. The existing Fiji Ditch will be
18 improved. North Area C area may also be graded so that rainfall flows into and supports seasonal wetlands
19 and other upland habitats. Elevations will vary as ultimately determined by the soil volumes necessary,
20 but are expected to range from 30 to 40 feet, or from a ten to thirty feet above Culver Boulevard. Grades
21 are currently from ten to fifteen feet above Culver Boulevard.

22
23
24 If the excess soil volume is less than the preliminary design estimate, less earth disposal in Area C will be
25 required. Reduced filling could result from lower in situ soil density in Area A or more substantively if
26 another entity agrees to accept and transport the excess soil material off-site. Depending on the actual soil
27 disposal requirement, the design of Area C may be revised. For example, the grades could be left as is or
28 the northwest portion of Area C could be restored to tidal wetland connected to Fiji Ditch as an option
29 within the Project design.

30 2.9.2.2 *Area C South*

31 The following section is based on information provided by the Annenberg Foundation, who is leading
32 planning and design of a visitor center in Area C South.

33
34
35 Area C South is roughly bounded by Ballona Creek to the southeast, the State Route 90 (the Marina
36 Freeway) to the northeast, Culver Boulevard to the west, and the Culver Boulevard/Lincoln Boulevard
37 intersection to the southwest. New visitors' facilities would be created in Area C South. The Annenberg
38 Foundation in partnership with the Department of Fish & Wildlife would design, construct, maintain, and
39 operate the Ballona Interpretive Center and supporting infrastructure. The Ballona Interpretive Center
40 would have five primary components (Interpretive Center, habitat restoration, walking trails system,
41 bicycle access, ball fields and parking) and would involve:

- 1 1. Creating an interpretive center of approximately 46,000 square feet (enclosed space) to
- 2 fulfill a variety of interpretive and programmatic functions;
- 3 2. Restoring native habitat by removing invasive species and regrading and replanting with
- 4 native species;
- 5 3. Creating walking trails and bike paths with interpretation in the native uplands habitat
- 6 and connecting to the existing Ballona Creek bike path and greater BWER;
- 7 4. Replacing existing parking on gravel with environmental “best practices” parking and
- 8 include a new curb cut for access to Culver Boulevard;
- 9 5. Enhancing the current ball fields to allow for Little League use 3-4 months a year and
- 10 other public access uses for the remainder of the year;

11 **Site Development:**

12 Development in Area C South would include an Interpretive Center. The overall architectural space
13 would be approximately 46,000 square feet, with a footprint of approximately 33,000 square feet. The
14 center would contain both visitor-serving elements and exhibits and multi-purpose program spaces
15 designed to provide a variety of learning opportunities for adults and school-aged children. The building
16 would house three categories of uses: educational space (50 percent of the building), administrative space
17 (25 percent), and live animal support space (25 percent).

18
19
20 The structure would consist of concrete over metal deck and structural steel. Foundations would consist
21 of piers or piles due to the soft soil conditions and the potential presence of methane gas. The facility
22 would include green roofs and berming around the building to integrate it into the landscape.

23
24 An upland habitat zone would be established over approximately 15 acres of the Area C South. This
25 habitat restoration would maximize wildlife adjacencies with the remainder of the BWER habitats. In
26 conjunction with the overall biological intent for the Reserve, invasive plants listed by Cal-IPC as
27 “moderate” or “high” would be targeted for removal. Planting areas would be cleared and grubbed to
28 remove existing trees, shrubby growth and brush, vines, ground covers, stumps, roots, weeds, stones,
29 wood and trash. An ongoing maintenance program consistent with the CHAMP would continue to
30 monitor and remove invasive species. The planting palette and principles behind the creation of
31 underlying habitat would be controlled by and consistent with the CHAMP with the following exceptions:
32 1) A permanent drip irrigation system would be used to irrigate landscape along the entry drive and
33 immediately around the building’s public and private areas; 2) The native turf areas at the multi-purpose
34 fields would be irrigated by a permanent system of pop-up rotary or sprinkler heads. Otherwise, new
35 upland planting would be irrigated with a two-year temporary system of pop-up rotary or sprinkler heads
36 to establish plants.

37
38 Approximately 4,800 linear feet of fully accessible pedestrian trails would be developed throughout Area
39 C South, connecting amenities and habitat zones, and providing access to the Ballona Creek bicycle trail
40 as well as trails in the remainder of the BWER. Trails would range in width from 6 to 12 feet, and would
41 be constructed of materials that would demonstrate high permeability, such as stabilized decomposed
42 granite and/or wooden boardwalks. The walking trails would encompass between 0.75 and 1.25 acres of
43 Area C south.

1 The new paths would provide scenic detours, allowing slower observation separated from the existing
2 path. These detours loops would extend no more than 100 feet from the existing bike path. The bike
3 loops would also be fully accessible, approximately 6 to 12 feet wide, and surfaced with decomposed
4 granite or compacted gravel to provide permeability. A gateway node along one of the detour would
5 provide an area for cyclists to dismount, park, and secure their bicycles in order to access the remainder of
6 Area C South on foot. Bike traffic would be limited elsewhere within Area C South, for safety of
7 pedestrians and habitat protection.
8

9 Development in Area C south would include the reconfiguration of the existing ball fields. Currently
10 these ball fields occupy approximately 6.2 acres of land. The ball fields would be reconfigured and
11 enhanced with native plant materials to increase the total vegetated area of the site and improve the
12 compatibility of the recreational and habitat areas. The existing concession building would be
13 reconstructed within a newly created berm.
14

15 The existing dirt parking area for approximately 250 cars would be replaced with two smaller parking
16 areas designed for environmental compatibility. Parking for 150 cars would be located adjacent to the
17 reconfigured ball fields. This parking would also be used for bus parking for school and other group
18 outings. The remaining 100 spaces for cars would be relocated to a linear parking area, parallel to Culver
19 Boulevard, with an additional driveway located at least 600 feet southwest of the existing Culver
20 Boulevard intersection with the eastbound on-ramp to the Marina Freeway.
21

22 All proposed program elements for Area C South would avoid encroachment on the narrow drainage
23 swale on the eastern edge of the site defined by the U.S. Army Corps of Engineers as “wetland.” The area
24 lies at the toe of an embankment that would not be altered nor impacted by the proposed layout of new
25 design elements. Efforts to enhance the biodiversity of plant life within this zone by selectively removing
26 non-native species and replacing with native wetland species would be developed.
27

28 **Grading and Drainage:**

29 The existing topography of Area C South is a relatively level at an average elevation of approximately 22
30 ft NAVD, which roughly joins the top of the existing Ballona Creek levee to the southeast. The site
31 slopes generally and gently from northeast to southwest with steeper slopes at the perimeter to join Culver
32 Boulevard to the west at an elevation of approximately 13 ft NAVD and the Marina Freeway to the north,
33 at an average elevation of approximately 13 ft NAVD. In addition there is an existing drainage basin to
34 the south adjacent to the Culver Boulevard/Lincoln Boulevard intersection.
35

36 The proposed grading for the site consists of earth moving to achieve a building pad with parking and
37 undulating site mounds, depressions, drainage paths, walking paths and bike paths across the entire
38 property. Up to approximately 100,000 cubic yards of soil excavated for the restoration will either be
39 exported off-site or transported across Culver Blvd. to south Area C. The height of earth mounds in
40 various parts of the site will be on the order of 10 feet above the existing grade or to an approximate
41 elevation of 32 ft NAVD.
42

1 Excavations, fill slopes, and structures would be set back from the Ballona Creek levee at least 100 feet
2 from the existing levee to avoid imposing surcharge loads on the existing levee. Grading within the 100-
3 foot setback zone would be minimal, would not exceed slopes of 5%, and would roughly match existing
4 grades.

5
6 The existing unpaved parking areas adjacent to the baseball fields would be re-designed to provide for
7 treatment of storm water runoff from the parking lot.

8
9 Storm water would be directed to existing storm water drainage facilities in Culver Blvd.

10
11 An “arroyo” feature will also be constructed to provide storm water functions and aesthetic values.
12 Storm water from the Interpretive Center and facilities will be directed to an “arroyo” feature. The arroyo
13 would extend into Area C North and connect to the existing Fiji channel, which would be enhanced to
14 improve habitat within the restoration.

15
16 Drainage for the proposed site would be collected on site through a network of graded surface swales and
17 channels and underground storm drainage conduits. Drainage would be directed to existing drainage
18 facilities in Culver Boulevard and to the existing drainage basin located to the south of the property
19 adjacent to the Culver Boulevard/Lincoln Boulevard intersection.

20 21 2.9.3 Seasonal Wetlands

22 Seasonal wetland may be created in the Area B and Area C upland fill areas. These areas would be graded
23 to direct rainfall runoff into shallow seasonal wetland depressions. The seasonal wetland areas would be
24 over-excavated by 1 to 2 feet and backfilled with compacted clay material to encourage ponding.

25 26 2.10 NATURAL GAS STORAGE FACILITIES

27 The Southern California Gas Company (SoCalGas) owns and operates natural gas storage wells and
28 associated pipelines within the Ecological Reserve property and holds easements over these areas. Some
29 of the wells in the restoration project area are not actively being used in the storage operations and can be
30 considered for abandonment without being relocated. Abandonment entails removing all near surface
31 components, which would eliminate constraints on restoration. Other wells are monitoring wells that are
32 necessary for storage operations and would need to be relocated. SoCalGas’ long-term plan is to
33 consolidate gas infrastructure within its property and facility along the southern bluff by abandoning gas
34 wells in the wetlands and installing replacement wells within their facilities to the extent possible. The
35 Project is working closely with SoCalGas to coordinate the restoration with gas infrastructure plans. The
36 coordinated plans involve three general priorities for gas infrastructure decommissioning:

- 37
38 1. Priority 1 (required for restoration): Certain gas wells and pipelines must be abandoned and/or
39 modified to facilitate the restoration, while other gas infrastructure can be avoided by the
40 restoration by protecting the infrastructure in place.
41 2. Priority 2 (desired for restoration): Abandonment of other gas infrastructure is desirable for the
42 restoration and to SoCalGas because it increases the extent of restoration and progresses
43 SoCalGas’ long-term plan; however, these modifications are not required for the restoration.

- 1 3. Priority 3 (desired by SoCalGas): The remaining gas infrastructure can be avoided by the
2 restoration without compromising the extent or function of the restoration, but is desired by
3 SoCalGas to accomplish their long-term plan.
4

5 SoCalGas conducts all work related to the facilities they own. Some gas infrastructure (e.g., some
6 abandoned wells and pipelines) may not be owned by SoCalGas, in which case the Project may conduct
7 any work needed to modify the infrastructure. SoCalGas' plans to decommission their onsite
8 infrastructure are dependent on funding. Figure 3 shows the Gas Company facilities and Appendix F
9 shows the gas infrastructure modification plan. The EIR/S will analyze the potential impacts associated
10 with the removal, abandonment and/or replacement of all gas infrastructure within the Ecological
11 Reserve.
12

13 2.10.1 Gas Infrastructure Decommissioning Plan

14 The prioritized plan for gas infrastructure decommissioning is included below.
15

16 Area A:

17 Priority 1 (required for restoration)

- 18 • Abandon inactive Area A pipeline
- 19 • Avoid Area A wells

20 Priority 2 (desired for restoration)

- 21 • Plug and abandon Del Rey (DR) 13 and 14
- 22 • DR 16 (abandoned) – re-abandon or over-excavated as needed to accommodate grading

23 Priority 3 (desired by SoCalGas)

- 24 • Drill a new well to main plant area to replace DR 19 (can be avoided by restoration)
 - 25 • Plug and abandon DR 15 and 17 (can be avoided by restoration)
 - 26 • Abandon active pipeline serving DR 18 (if Gas Co abandons DR 18 on Fiji/offsite)
- 27

28 Area B:

29 Priority 1 (required for restoration)

- 30 • Drill new wells to main plant area to replace DR 12 and plug and abandon DR 12 (to allow for
31 channel meander excavation)
- 32 • Plug and abandon Vidor 3 (as needed to allow for Culver levee fill placement)
- 33 • Modify pipeline from proposed Culver levee to existing Creek crossing (e.g., replace section of
34 pipe at lower elevation to accommodate levee construction and wetland restoration). Note that
35 this pipeline may be abandoned (see Area A, Priority 3)

36 Priority 2 (desired for restoration)

- 37 • Drill new wells to main plant area to replace DR 9
- 38 • Plug and abandon DR 4 and 5 and Vidor 1 and 2

39 Priority 3 (desired by SoCalGas)

- 40 • Drill new well to main plant area to replace Vidor 18
 - 41 • Plug and abandon DR 11 and Vidor 5 and 14
- 42

43 Note: Vidor 4 (abandoned) – re-abandonment is assumed to not be necessary to allow for eventual tidal
44 restoration

1 Abandonment must occur prior to construction, or grading will be conducted around the facilities to avoid
2 impacts. At a minimum, the project plans to abandon the Priority 1 wells listed above. New wells drilled
3 to replace abandoned wells will be drilled within the Gas Co property along the southern bluff.
4

5 During construction, wells that are to remain (e.g., for the Interim Build Out) will be provided a setback
6 and flood protection. Flood protection will primarily consist of construction of a levee around well areas
7 that are below flood elevations. Full-time all-weather access for heavy equipment will need to be
8 maintained to all wells that remain.
9

10 2.10.2 Interim Build Out Well Abandonment

11 For the Interim Build Out, wells in Area A would be abandoned according to the priorities above. This
12 area will be restored to upland habitat and excavated to create transition habitat sloping down to
13 marshplain as shown in Figures 5A - 5C. DR 17 along Fiji Way will be avoided by constructing the new
14 Area A perimeter levee to the east of this well.
15

16 If wells in Area A are not abandoned within the time frame for the Interim Build Out, the wells to remain
17 will be avoided. The wells in Area A are currently above flood elevations. The Project would restore
18 upland habitat and/or excavate around any wells to create sloping upland transition habitat. Once the
19 wells are abandoned, the area will be graded and restored as shown in the Interim Build Out.
20

21 Within Area B, DR 12 will be abandoned to allow for the channel realignment in the Interim Build Out.
22 Vidor 3 will also be abandoned as needed to allow construction of the new Culver levee. The temporary
23 levee between the new Culver levee and the existing south Ballona Creek levee along West Area B will
24 be constructed to protect and avoid the cluster of wells in West Area B, which includes Vidor 1 and 2 and
25 DR 4, 5, and 9. The Interim Build Out allows for these wells to be maintained as is or to be abandoned to
26 facilitate restoration to marsh connected to West Area B during Full Build Out. The project plans to avoid
27 Vidor 18 by aligning the new West Area B levee to the north of this well.
28

29 2.10.3 Full Build Out

30 For the Full Build Out, Vidor 1 and 2 and DR 4, 5, and 9 in West Area B would be abandoned to allow
31 for full tidal restoration of West Area B. If these wells are not abandoned within the timeframe of the Full
32 Build Out, a levee will be constructed around the wells between the Culver levee and the Interim Build
33 Out temporary levee to create a ring levee around the wells. A drainage culvert would be installed in the
34 levee to provide storm drainage. Once the wells are abandoned, the ring levee will be removed to restore
35 habitats as shown for the Full Build Out (Figure 5C). The project will lower any levees to create the
36 upland peninsula, transitional and marsh habitats.
37

38 2.10.4 Pipeline Protection and Relocation

39 Appendix F shows the gas pipeline relocation plan. The section of the gas pipeline between the new
40 Culver levee and the existing Creek crossing to Area A would be modified to allow levee construction
41 and wetland restoration (e.g., by replacing the section of pipe at lower elevation and by placing the pipe in
42 a sleeve under the new Culver levee to address the potential of differential settlement of the pipeline)
43 This entire pipeline may be abandoned once wells in Area A are abandoned.

1 In East Area B, the portion of the Line 1167 30-inch natural gas transmission pipeline crossing the
2 wetland to Jefferson Blvd. will be relocated along the Gas Company Road (see Section 2.10.4 and
3 Attachment F). These relocations must be completed prior to grading within their respective areas. Other
4 gas pipelines to remain in place will be avoided by setting earthwork back by an appropriate distance.
5

6 The existing abandoned pipeline through Area A and along the north Ballona Creek levee will be capped
7 at both ends beyond the limits of restoration earthwork. The abandoned pipeline section within Area A
8 will be removed as needed for restoration grading. Other abandoned pipelines may be encountered during
9 restoration grading and will be removed. Other pipelines can remain in place and will be set back an
10 appropriate distance.
11

12 2.11 ENGINEER'S ESTIMATES

13

14 Preliminary estimates of earthwork quantities and construction costs have been developed based on the
15 preliminary grading plans and design approaches described in this PDR.
16

17 2.11.1 Earthwork Quantities

18 The engineer's estimate of earthwork volumes is provided in Table 5. At this preliminary design level, the
19 earthwork volume estimates indicate that the project will include excavation of about 2,170,000 cubic
20 yards of material (in-place). Material for creation of levees, upland transitional habitat, and marsh
21 topographic features including islands, berms, pans, and seasonal wetlands will include placement of
22 about 1,420,000 cubic yards of excavated material (based on in-place excavation volumes adjusted for
23 density changes). The net offhaul to the onsite upland fill placement areas in Area B and Area C is about
24 770,000 to 870,000 cubic yards, and the preliminary grading plans for these fill placement areas provide
25 about 870,000 cubic yards of capacity including an allowance of 100,000 cubic yards of fill placement in
26 Area C South or off-site export.
27

28 Mass earthwork volume estimates was prepared using AUTOCAD Civil 3D software by examining
29 volumetric differences between existing grade based upon the site base topography prepared by PSOMAS
30 and the preliminary grading plans for presented in previous sections. The mass grading estimates were
31 further refined to account for density changes between in-place excavation of primarily, loosely
32 consolidated material in Area A to compacted fill placed in lifts primarily for levees and stability berms.
33 At the preliminary stage, a volumetric reduction of 15 to 25 percent was assumed between in-place
34 excavation and in-place fill. In addition, settlement estimates for levees in Area A and Area B were
35 incorporated into estimates of levee core volumes reflecting about 2 inches of settlement per foot of fill.
36 Estimates of volumetric changes due to compaction and settlement were based upon preliminary
37 recommendations documented the Preliminary Geotechnical Design Summary. Earthwork estimates for
38 levees also reflected the geotechnical recommendations for subgrade preparation including over-
39 excavation and compaction. The earthwork estimates will be updated based upon the recommendations
40 included in the Final Geotechnical Design Report.
41

42 Estimates for excavation of tidal channels within Area A and North Area B assumed that all channel
43 material excavated from these areas would be utilized to create upland transitional fill or placed in the

1 Area B and C fill placement areas. Channels excavated in West, South, and East Area B assumed that all
2 excavated material would be side cast to create low berms adjacent to the excavated channels. This
3 approach limits the need to truck material out of these areas that currently support sensitive existing
4 marsh habitat.

5
6 The preliminary earthwork estimates do not reflect special handling of any materials that do not meet the
7 wetland cover or upland cover standards or any hazardous materials. Following completion of the soils
8 analyses to better understand the level and extent of any existing impacts and consultation with the
9 regulating agencies regarding appropriate standards for materials classification, handling, and cover
10 depths, the earthwork quantities will be refined to reflect any special handling that is anticipated.

11
12 2.11.2 Cost Estimates

13 A list of items of work is included in the Table 6. The items of work provides major project elements
14 related to earthwork, rock/soil cement slope protection, bridges, public and County access, and plantings.
15 These work items are provided along with the anticipated measurement unit for the construction contract.

16
17 As the design is refined, the work items table will be updated to reflect total units and unit costs for each
18 work item to develop a construction cost estimate.

19

Table 5: Preliminary Estimates of Earthwork Volumes

WORK ITEM	CUT CY	Average	Min	Max
		FILL* CY	FILL* CY	FILL* CY
AREA A				
PERIMETER LEVEE				
Levee Subgrade & Keyway	25,200	30,200	29,000	31,500
Levee Core - Compacted Fill + Settlement	-	34,600	33,100	36,000
Outboard Stability Berm	-	16,400	15,700	17,100
Inboard Stability Berm	-	36,100	34,600	37,600
Levee Road Surface	-	3,100	3,100	3,100
PERIMETER LEVEE - SUBTOTAL	25,200	120,400	115,500	125,300
WETLAND MASS GRADING				
Clearing & Grubbing	54,400	-	-	-
Mass Excavation to Marshplain & Transitional Slopes	990,500	-	-	-
Fill to Create Upland Mounds adjacent to Levee	-	28,400	27,200	29,600
Fill around Existing Gas Wells	-	30,500	29,200	31,700
WETLAND MASS GRADING - SUBTOTAL	1,044,900	58,900	56,400	61,300
WETLAND FINE GRADING				
Excavate New Tidal Channels	19,200	-	-	-
Tidal Pans	2,800	3,400	3,200	3,500
Seasonal Wetlands	4,400	5,300	5,100	5,500
WETLAND FINE GRADING - SUBTOTAL	26,400	8,700	8,300	9,000
GRADING ALONG NORTH BALLONA CREEK				
Excavation of North Meander Bend	193,100	-	-	-
Excavation of West Breach	35,600	-	-	-
Excavation of East Breach	53,900	-	-	-
Lower North Ballona Creek Levee	117,300	1,100	1,000	1,100
Grading of Existing Channel	26,100	46,100	44,200	48,000
Fill West Channel Meander	-	102,700	98,400	107,000
EXCAVATION ALONG BALLONA CREEK - SUBTOTAL	426,000	149,900	143,600	156,100
AREA A SUBTOTAL - Interim Build Out, Option A				
	1,522,500	337,900	323,800	351,700
AREA A Well Lowering				
Lowering Well pad and regrading	208,000	8,800	8,400	9,100
AREA A SUBTOTAL - Interim Build Out, Option B				
	1,730,500	346,700	332,200	360,800
AREA B				
CULVER LEVEE				
Levee Subgrade & Keyway	7,800	9,800	9,400	10,100
Levee Core - Compacted Fill + Settlement	-	59,300	56,800	61,800
Outboard Stability Berm	-	84,200	87,700	80,700
Inboard Stability Berm	-	62,100	59,500	64,700
Levee Road Surface	-	1,700	1,700	1,700
CULVER LEVEE - SUBTOTAL	7,800	217,100	215,100	219,000

Table 5: Preliminary Estimates of Earthwork Volumes

WORK ITEM	CUT CY	Average	Min	Max
		FILL* CY	FILL* CY	FILL* CY
INTERIM AREA B LEVEE				
Levee Subgrade & Keyway	2,800	3,500	3,400	3,600
Levee Core - Compacted Fill + Settlement	-	46,900	45,000	48,900
Outboard Stability Berm	-	29,400	28,100	30,600
Inboard Stability Berm	-	84,900	81,400	88,500
Levee Road Surface	-	700	700	700
INTERIM AREA B LEVEE - SUBTOTAL	2,800	165,400	158,600	172,300
WEST AREA B LEVEE				
Levee Subgrade & Keyway	10,800	13,500	13,000	14,000
Levee Core - Compacted Fill + Settlement	-	181,600	174,000	189,100
Outboard Stability Berm	200	51,100	49,000	53,300
Inboard Stability Berm	-	136,400	127,900	145,000
Levee Road Surface	-	2,300	2,300	2,300
WEST AREA B LEVEE - SUBTOTAL	11,000	384,900	366,200	403,700
NORTH AREA B WETLAND GRADING				
Clearing & Grubbing	25,000	-	-	-
Grading to Create Marshplain	43,900	100	100	100
East Habitat Peninsula	5,900	2,300	2,200	2,400
Excavate New Tidal Channels	6,900	-	-	-
NORTH AREA B WETLAND GRADING	81,700	2,400	2,300	2,500
GRADING ALONG SOUTH BALLONA CREEK				
South Meander Bend	84,700	-	-	-
Excavation of Breaches	82,300	100	100	100
Lower South Ballona Creek Levee	48,900	700	700	700
Fill East Channel Meander	-	112,200	107,800	116,700
GRADING ALONG SOUTH BALLONA CREEK - SUBTOTAL	215,900	113,000	108,600	117,500
WEST, SOUTH & EAST AREA B RESTORATION				
Excavate South Area B Channels	6,100	6,100	6,100	6,100
Excavate East Area B Channels	3,300	3,300	3,300	3,300
Excavate West Area B Channels	4,600	4,600	4,600	4,600
Lower Interim Levee	86,800	700	700	700
Fill Habitat Peninsula	200	38,900	38,900	38,900
Lower and Breach South Ballona Creek Levee	21,700	69,100	69,100	69,100
WEST, SOUTH & EAST AREA B RESTORATION - SUBTOTAL	122,700	122,700	122,700	122,700
AREA B SUBTOTAL	442,000	1,006,000	974,000	1,038,000
AREA A & B TOTAL	2,172,500	1,352,700	1,306,200	1,398,800
AREA C & AREA B - NET FILL PLACEMENT REQUIRED		819,800	866,300	773,700

Table 5: Preliminary Estimates of Earthwork Volumes

WORK ITEM	CUT CY	Average	Min	Max
		FILL* CY	FILL* CY	FILL* CY
FILL PLACEMENT AREAS				
Area C North	-	500,000		
Area C South (or off-site export)	-	100,000		
Area B - Between Jefferson & Culver	-	270,000		
TOTAL AVAILABLE FILL PLACEMENT MOUNDS	-	870,000		

* Fill Volumes for select earthwork items increased by 20% (avg) and 15% (min) to 25% (max) to account for volume differences between cut volumes and compacted, inplace fill.

Table 6: Schedule of Work Items for Future Cost Estimates

WORK ITEM	Quantity	Unit	Unit Cost	Item Cost
Mobilization				
Initial Mobilization	1	LS		
Seasonal Mobilization	7	LS		
Water Control (by Season)	7	LS		
Access Control (by Season)	7	LS		
Stormwater Management (by Season)	7	LS		
Demo				
Abandon Gas Well	1	LS		
Channel Armoring	9,900	LF		
Freshwater Marsh Outlet Headwall	1	LS		
Culver Road Culvert	1	LS		
West Area B Water Control Structure	1	LS		
Gas Well Access Road Culvert	1	LS		
Earthwork				
Perimeter Levees				
Area A Levee	120,400	CY		
Culver Levee	217,100	CY		
Temporary Area B Levee	165,400	CY		
West Area B Levee	384,900	CY		
West Area B Levee - Completion	69,100	CY		
Levee Armoring				
Type 1	?	LF		
Type 2	?	LF		
Type 3	?	LF		
Marsh & Transitional Grading				
Area A	1,103,800	CY		
Area A - Well Pad Lowering	208,000	CY		
Area B North	69,000	CY		
Wetland Fine Grading - Channels, Pannes and Ponds				
Area A Tidal Channels	19,200	CY		
North Area B Tidal Channels	6,900	CY		
East Area B Tidal Channels	3,300	CY		
South Area B Tidal Channels	6,100	CY		
West Area B Tidal Channels	4,600	CY		
Seasonal Wetlands	4,400	CY		
Tidal Pannes	2,800	CY		
Create Upland Peninsulas	47,000	CY		
Culver Road Detention Basin & Swale	?	CY		

Table 6: Schedule of Work Items for Future Cost Estimates

WORK ITEM	Quantity	Unit	Unit Cost	Item Cost
Ballona Creek Realignment				
Excavate Meanders	277,800	CY		
Fine grading In Channel	72,200	CY		
Breach Levees	171,900	CY		
Fill Meanders	214,900	CY		
Lower Levees	168,000	CY		
West Area B Restoration				
Breach Levee	?	CY		
Lower Levee	21,700	CY		
Water Control Structures				
Culver/Jefferson East Area B Structure				
Culverts - X, Y dia	?	LF		
Headwalls	?	EA		
Gates	?	EA		
Culver / South Area B Structure				
Culverts - X, Y dia	?	LF		
Headwalls	?	EA		
Gates	?	EA		
West Area B Structure				
Culverts - Y dia	?	LF		
Headwalls	?	EA		
Gates	?	EA		
Culver Road Detention Basin				
Culverts - Y dia	?	LF		
Headwalls	?	EA		
Gates	?	EA		
Public Access				
Pedestrian, Bicycle & Construction Bridge				
Piers	?	EA		
Bridge	?	LF		
Access Trail/Road	?	LF		
Access Control - Bollards/gates	?	EA		
Signs	?	EA		
Planting/Erosion Control				
Upland Plantings				
X Containers	?	EA		
Hydroseeding	?	AC		
Transitional Plantings				
X Containers	?	EA		
High Marsh Plantings				
X Containers	?	EA		
Total Construction Cost				

1 Construction Methods and Phasing

2
3 2.12 CONSTRUCTION METHODS

4
5 There are several important considerations affecting construction:

- 6
- 7 • Transport of soil between Area A and Areas C and B, which entails crossing Ballona Creek and
- 8 or busy roadways;
- 9 • Levee Lowering and Breaching of existing levees to inundate Areas A and B, and new channel
- 10 meanders;
- 11 • Soil Bearing and Construction Equipment: Ground water elevation relative to finished grades,
- 12 which will affect the feasibility of using conventional construction equipment.
- 13 • Channel Excavation and Berm Fill. The project entails excavating channels in existing wetland;
- 14 • Re-alignment of the Ballona Channel, which entails filling the existing flood control channel;
- 15 • Stability of the existing levee along the north side of Ballona Creek during excavation of Area A;
- 16 • Relocation of interfering utilities;
- 17 • Construction or support of new drainage facilities to avoid upstream drainage impacts;
- 18 • Interim stockpiling of soils between phases;
- 19 • Drying of soils to re-use as structural fill;
- 20 • Environmental windows and habitat establishment (previously discussed);
- 21 • Clearing and grubbing to allow for grading and treatment of invasive vegetation removed;
- 22 • Revegetation of restored habitats;
- 23 • Gas well abandonment and replacement process;
- 24 • Other considerations.
- 25

26 These considerations are addressed in the following sections.

27
28 2.12.1 Soil Transport

29 The intent for our grading design is that at the completion of construction, we will be balanced on-site.
30 This means that no import or export of soils is anticipated other than if contaminated soils are discovered
31 at levels that require offhaul and offsite disposal. And volumes for these are expected to be negligible
32 from a grading quantities standpoint. Therefore truck routes and other transport methods should be
33 limited to the projects areas and the immediately adjacent roadways. A series of exhibits are provided
34 showing the routing options expected.

35
36 Soil transport is expected to be accomplished using one or more of the methods identified in Table 7. The
37 likelihood of different construction methods will be revisited based on additional geotechnical analysis of
38 soil conditions.

39
40 Wheeled scrapers and trucks can traverse adjacent roadways, but the strong preference is to provide
41 routes that limit the requirement to impact roadways. This puts a premium on installation of a bridge or
42 crossing across Ballona Creek, and a temporary bridge across Lincoln Boulevard. Both options are
43 available which could leave the transport of soils to the uplands areas of east Area B as the only area that

1 would require transport on roadways. The relatively small volumes of soils this area is capable of
 2 accepting may make it cost prohibitive to do anything other than simply crossing Culver.

3

4 **Table 7 Earthwork Transport Options**

Method	Associated with	Cost	Conditions	Application
Scrapers	Self contained	Low unit cost	Dry, firm, open	Within Area A, and if possible to C and portions of Area B,
Trucks	Excavators, Dozers	Moderate unit costs, with multiple handling		Possible means to reduce impacts to crossings between areas and support to other methodology listed
Conveyor	Excavators, Dozers, Trucks	Moderate unit cost plus mobilization	Confined without vehicular access	Possible means of crossing Ballona Creek and roads
Low ground pressure	Excavators, Dozers, Trucks, Mats	High unit cost	Wet, weak	Anticipated for areas below groundwater elevation, wetland channel excavation and sidecast berms
Hydraulic	Dredge	High mob, low unit cost	Open water, ample water supply	Not anticipated but possible in lowest areas

5

6 Photographs of a conveyor in operation are provided in Appendix E.

7

8 *2.12.1.1 Across Ballona Channel*

9 Methods for moving earth across Ballona Channel are provided in Table 8.

10

11 **Table 8 Ballona Creek Crossing Methods**

Method	Appropriate Equipment		Conditions	Application
	Expected	Possible		
Existing Bridge	Trucks	Scrapers	Road closures, restricted hours	Use Culver, close one direction during selected dates and times
Temporary Bridge	Trucks, Scrapers	Conveyor	Mobilization	Use old railway alignment to cross Lincoln and or Ballona Creek
Barge / floating crossing	Scrapers, Trucks	Conveyor	Mobilization, dry season	Straight between A and B across Ballona; wide enough for scrapers
Temporary ford	Scrapers, Trucks	Conveyor	Mobilization, dry season	Two options: (1) straight between A and B and (2) along north bank under Culver and Lincoln Bridges
Permanent Bridge	Scrapers, Trucks	Conveyor	Mobilization, phasing	Crossing Ballona Creek
Culver	Conveyor		Limited space, dry season	Fiji channel from A under Lincoln to C North under Culver to C South

12

13

1 2.12.1.2 *Across Roadways*

2 See Table 8, above, for Ballona Crossing. Additional consideration is needed to determine how to get
3 earth between Culver and Jefferson using Ballona Crossings other than the existing Culver roadway or a
4 new bridge that crosses Culver as well.
5

6 2.12.2 Levee Lowering and Breaching

7 Levee lowering involves a phased removal of earth to maximize the quantity that is moved prior to
8 breaching and to limit the risk of uncontrolled breaching. The figure “Levee Lowering” in Appendix E
9 shows how this work is staged. In multi-year construction, the minimum section of earth levee to remain
10 through the winter is specified (e.g. “Phase 2” in drawing). The construction contractor is also required to
11 sequence his work to prevent site inundation, and typically does this by leaving a small raised area (e.g.
12 the “check berm” in the photograph) until final earthwork. The final earthwork often consists of dozer
13 operation to quickly remove the check berm and side cast earth into the site. This last work may be timed
14 for a neap tide (approximately one week period) and staged to maintain egress along portions of the levee
15 (that is, consideration of access and breach locations) to facilitate phased lowering as portions of the
16 project are completed. Alternatively the contractor may use steel sheet pile coffer dams along the levee to
17 allow for levee lowering at all tide levels.
18

19 Breaching is also phased, similar to levee lowering. If possible, shoring is avoided because installation
20 and removal induce additional environmental impacts and costs. The breaching is usually accomplished
21 by two long reach excavators working on the lowered levee on either side of the breach to be excavated.
22 At first, earth may be loaded to trucks and taken elsewhere. However, once the levee section is reduced to
23 the point of incipient breaching at the next high tide, the operation shifts into a high production rate mode
24 with excavated material sidecast. Often, other excavators and low-ground pressure dozers re-handle the
25 side cast earth and displace it farther away from the breach, thereby limiting the height of the side cast
26 and maximizing the excavation rate. The work continues until the breach is excavated or the tides
27 approach the levee surface. For larger breaches, multiple days or weeks may be required, resulting in
28 relatively high potential velocities. In this case, an internal and potentially external earth berm (sometimes
29 called a “donut” or “dredge lock”) can be constructed to limit the area of impact during construction.
30 Steel sheet pile coffer dams may also be used to limit tidal inundation of breach excavations. See Figure
31 “Breaching” in Appendix E.
32

33 2.12.3 Soil Bearing and Construction Equipment

34 Much of the Ballona earthwork may be accomplished by traditional land based equipment. In particular,
35 the maximum use of scrapers will provide the greatest economy.
36

37 Wetland restoration construction requires special equipment and construction methods. High ground
38 water and weak soils can preclude use of traditional land equipment and increases the unit costs of
39 construction. The Construction Equipment figure in Appendix E provides pictures of some examples.
40 These are as follows:

- 41 • Low ground pressure: smaller, lighter equipment with large surface area tires or treads that reduce
42 bearing pressure.
43

- 1 • Mats: Timber planks (thick) lashed together and moved by bucket-type equipment.
- 2 • Long reach excavator: Track or wheel mounted excavator with a long arm and small bucket to
- 3 allow extended reach to over 40 feet.
- 4 • Clamshell and Dragline Crane: Usually track mounted, can reach 60 feet or more.
- 5 • Amphibious Excavator: Can float, and can excavate in shallow standing water.
- 6 • Rotary Ditcher: Excavates with rotating wheels that spray sediment across adjacent areas,
- 7 resulting in a narrow ditch. Typically pulled behind other equipment but can be self propelled.
- 8 • Floating equipment: Cranes and excavators can be floated on barges for both transport and
- 9 operation. Equipment can be trucked in and assembled to work in land-locked water bodies.
- 10 • Hydraulic dredge: A water and sediment mixture can be excavated and pumped. (Not expected in
- 11 this project)

12

13 2.12.4 Tidal Channel Excavation and Earth Berm / Terrace Fill

14 PWA has developed and implemented approaches for restoring tidal marsh morphology using limited
 15 earthwork, strategically configured to limit costs and intervention, that lead to enhanced and more rapid
 16 habitat establishment. Tidal channel and marsh berm construction are one of the tools used. The concept
 17 is depicted in the Tidal Channel and Berm Figure in Appendix E. Channels are excavated and material
 18 side cast to form low height, flat sloped embankments (berms). The berms are shaped by the excavation
 19 bucket and or other equipment, but are not typically compacted. An exception is berms placed above tidal
 20 wetland for riparian or wetland forest habitat, which are more readily compacted.

21

22 2.12.5 Ballona Channel Realignment

23 The project includes a realignment of Ballona Channel from a straight to a meandering planform. This
 24 will require filling the existing channel. We anticipate that this can be accomplished with the following
 25 construction sequence:

- 26
- 27 • The new channel is excavated
- 28 • The new channel is breached
- 29 • The old channel is blocked on the upstream and downstream ends, with flows bypassing to the
- 30 new channel
- 31 • The old channel is filled between the blocked areas.

32

33 Blocking the channel can be accomplished in several ways:

- 34
- 35 • Rubble fill: A rock dike is constructed with floating equipment or “over the top” from land. The
- 36 rock is graded to have a wide range of sizes, limiting contiguous voids and subsequent sediment
- 37 migration.
- 38 • Sheet piling is placed. The plan form could be a linear wall with steel or concrete, or have a
- 39 cellular structure with steel.
- 40 • Precast concrete gravity structures, interlocking
- 41 • Use of temporary fabric and sheet structures such as
- 42 o Water or soil filled fabric tubes
- 43 o Metal frames and plastic sheets.

1 Filling the blocked channel can be accomplished several ways

- 2
- 3 • Dumping of earth from the sides; and building out
- 4 • Hydraulic slurry of sands, with subsequent earth moving above water
- 5 • Land based equipment in a dewatered condition.
- 6

7 Figure “Fill in Water” in Appendix E shows how islands and port fills are constructed.

8

9 Given that the Area A earth source is above grade and primarily silty, use of hydraulic dredge methods is
10 not preferred, but may be necessary in certain areas. Given that Ballona Creek is shallow and relatively
11 calm water, use of temporary fabric and sheet structures may be preferred. Dewatering of the fill area may
12 be practical, and land based equipment may be used.

13

14 2.12.6 Construction Period Levee Stability

15 Construction period levee stability will be addressed by staged construction with geotechnical
16 recommendations.

17

18 Levee construction often requires a phased construction to compensate for settlement and to avoid
19 overloading the subgrade and causing shear failure and mass movements. The increased weight of an
20 earth levee will typically result in consolidation of underlying soils and settlement. The increased weight
21 will also increase the shear stresses in the foundation soils, and can cause shear failure and deformation,
22 and greatly compromise the levee construction. Consequently, levee construction often requires a second
23 construction phase one or more years later to compensate for settlement. The risk of slope failure can be
24 reduced and the rate of construction increased by using flatter slopes. Conceptually, placing more material
25 with a flatter slope reduces the gradient in loading and the maximum shear stress in the underlying earth.
26 The Levee figure in Appendix E shows examples of mud levees on weak soils with “stability berms.”
27 Stability berms are an additional mass, typically in the form of a bench or terrace, beyond the “core” of
28 the levee. The stability berms can provide attributes such as ecologic ecotone, wave protection and
29 access. The Levee figures and photos in Appendix E shows a two phase construction with anticipated
30 initial settlement.

31

32 2.12.7 Clearing and Grubbing and Invasive Plant Material Treatment

33 Vegetation will be cleared and grubbed prior to grading. Native plants can be salvaged and reused for
34 revegetation of restored areas. Invasive plants will be stockpiled on-site and treated (e.g., composted).
35 The preferred approach will be to bury invasive plant material in upland fill areas at a depth below which
36 the invasive vegetation cannot reestablish. WRA’s draft RAMP discusses this consideration and future
37 phases of the design will detail the approach for handling invasive vegetation.

38

39 2.12.8 Revegetation

40 WRA has developed a draft Conceptual Restoration and Adaptive Management Plan (RAMP) that
41 includes a conceptual revegetation plan and outlines revegetation design considerations. The RAMP and
42 subsequent revegetation design will be incorporated into future phases of the Project design. Revegetation
43 of restored wetland areas will rely on natural recruitment (see Section 2.5.1), with the possibility of

1 targeted installation of salt marsh vegetation as discussed in the RAMP. Transition zone and upland
2 habitats will required active revegetation and irrigation. The suitability of topsoil for target vegetation is
3 an important consideration (see Section 2.2.3) and management of topsoil may be required, particularly
4 for revegetated upland areas where soil amendment or leaching of soil salinity may be needed.
5

6 2.12.9 Gas Well Abandonment and Replacement Process

7 The following information was provided by SoCalGas on the process for abandoning gas wells and
8 drilling new wells to replace abandoned wells.
9

10 2.12.9.1 *Site Preparation*

11 Access Roads: Two inches of compacted ¾-inch base rock will be used to bring the access roads to the
12 wells to 12 feet in width on the straightaways and 20 feet in width at the corner of the turns, and capable
13 of supporting standard highway permitted trucks up to 80,000 pounds.
14

15 Well Site Locations: Two inches of compacted ¾-inch base rock will be used to create a work pad 120
16 feet by 170 feet centered at the wellhead.
17

18 The project duration will require a minimum of five (5) working days per well.
19

20 The following parameters are required to effectively provide for the abandonment of gas storage wells
21 operated by SoCalGas in the Ballona Wetlands:
22

- 23 • Certain well abandonments will need to be undertaken before the levees are removed, to avoid
24 flooding of the wellsite locations.
- 25 • Other wells will need to be abandoned prior to grading activity.
- 26 • If wells are being replaced, replacement wells must be drilled and determined to be successful
27 before the well being replaced is abandoned.
28

29 Once the wells are abandoned, the restoration of the wellsite locations can be undertaken in conjunction
30 with the planned restoration grading and site construction planned by the Ballona Wetlands Restoration
31 Project.
32

33 2.12.9.2 *Well Abandonment*

34 Well abandonment should be undertaken after the access road and the well site location have been
35 prepared. The process of abandoning a well includes bringing in a workover rig to remove downhole
36 piping and setting cement plugs to isolate the producing zones. The wellhead is removed and the well
37 casing is cut and capped approximately five (5) feet below grade. All concrete cellar material and piping
38 is then removed.
39

40 Each well abandonment will require a minimum of 30 to a maximum of 45 12-hour work days (8 AM to
41 8 PM) to complete.
42
43

1
2 The following equipment will be required to complete the well abandonment work:

- 3
4 1 - Mobile Production Rig with 106-foot high mast
5 1 - Mobile Rig Pump with engine and circulating pit with shaker
6 1 - Solids Bin
7 1 - Rig Equipment Truck
8 1 - Portable Generator
9 1 - Rig Crew Trailer
10 2 - 500 bbl portable liquid storage tanks
11 1 - Roll Off Trash Bin
12 2 - Roll Off Cement Bins
13 1 - Portable Restroom and Service Truck
14 1 - Cement Pump Truck
15 1 - Bulk Cement Truck
16 3 - Wireline Logging Trucks (USIT/perforating/Misc. tools)
17 1 - 120 bbl or 80 bbl Vacuum Truck
18 6 - Service Pickup Trucks (various onsite contractors)
19 1 - Delivery Truck (Tractor/Flatbed Trailer)
20 1 - Stinger Truck with flatbed trailer

21
22 Each wellsite will need to be accessible to install soil gas monitoring probes and monitor for gas leakage
23 for two months following abandonment. If no gas leakage is detected during the initial two month period
24 following abandonment, direct access to the well will no longer be required. If gas leakage is detected,
25 deeper probes will need to be installed and monitored for six months. After it has been determined that
26 there is no further gas leakage, the probes can be removed. SoCalGas will continue to conduct well gas
27 leakage surveys on each abandoned well every six months. In the case of the well subsequently being
28 submerged under water, another means of monitoring the well will be determined, such as checking for
29 gas bubbles percolating in the water above the abandoned well.

30
31 If well leakage occurs that requires re-abandonment, then the appropriate responsible entity (SoCalGas or
32 the State) will re-establish roads and wellpads to execute such work.

33 34 *2.12.9.3 Drilling New Well*

35 The process of drilling a new well involves moving in a large rig capable of working 24 hours per day and
36 having the necessary equipment to drill and install casing. The drilling rig is moved in on as many as 30
37 flatbed trucks and then assembled on location. Prior to move in, a cellar is first dug and shored using a
38 cellar ring or concrete walls. Then a conductor pipe is installed in the ground and the drilling rig is rigged
39 up. The drilling operation involves directional drilling a hole to the zone of interest. Once the hole is
40 drilled to the proper depth, casing is installed and cemented in place. The drilling rig is then disassembled
41 and moved out of the location. A smaller work-over rig is then needed to complete the well by installing
42 tubing and other completion equipment.

1
2 Each new well will require a minimum of thirty-five to a maximum of fifty 24-hour work days.
3 The following equipment will be required to complete the drilling of a new well:
4

- 5 1 - Drilling Rig with substructure, catwalk, drawworks, 149-foot high mast, with 11-inch Class IIIB
- 6 5M BOPE
- 7 2 - Skid Mounted Rig Pumps
- 8 1 - 600 bbl Mud Pit with shakers, circulating pumps, mud cleaner, centrifuge, mud mixing dock
- 9 2 - Solids Bins for drill cuttings
- 10 3 – Diesel (or NatGas powered) Electric Generators with SCR House
- 11 1 - Accumulator Unit
- 12 1 - Top Drive Power Unit
- 13 1 - Dog House/Tool Room/Crew Change Room
- 14 2 - Portable Generators
- 15 4 - 500 bbl portable liquid storage tanks
- 16 1 - Cement Pump Truck(s)
- 17 1 - Bulk Cement Truck(s)
- 18 3 - Wireline Logging Trucks (Open Hole Logging/USIT/perforating/Misc. tool running)
- 19 2 - 120 bbl or 80 bbl Vacuum Truck
- 20 1 - Roll Off Trash Bin
- 21 2 - Roll Off Cement Bins
- 22 1 - Portable Restroom(s) and Service Truck
- 23 8 - Service Pickup Trucks (various onsite contractors)
- 24 2 - Delivery Trucks (Tractor/Flatbed Trailer)
- 25 1 - Stinger Truck with flatbed trailer
- 26 4 - Residential Trailers (for onsite supervision)
- 27 1 - Mud Logging Trailer/Unit
- 28 1 - Directional Drilling Trailer/Control Room
- 29 1 - Casing Running Equipment/Crew
- 30 1 - Forklift (8 ton rated)
- 31 1 - Rig Equipment Truck
- 32 2 - 90 or 150 ton Cranes (for rig up/rig down)
- 33 30 to 50 Flat Bed Trailers and Trucks (for move in and move out)
- 34 1 - Backhoe

35
36 *2.12.9.4 New Well Completion Operations*

37 A workover rig is used to install the downhole tubing and associated monitoring equipment following
38 move out of the drilling rig. All surface piping including monitoring and instrumentation is then installed
39 after the workover rig is moved out.
40

41 Each completion will require seven to ten 12-hour work days (8 AM to 8 PM).
42
43

1
2 The following equipment will be required for the new well completion operations:

- 3
4 1 - Mobile Production Rig with 106-foot high mast
5 1 - Mobile Rig Pump with engine and circulating pit with shaker
6 1 - Rig Equipment Truck
7 1 - Portable Generator
8 1 - Rig Crew Trailer
9 2 - 500 bbl portable liquid storage tanks
10 1 - Roll Off Trash Bin
11 1 - Portable Restroom and Service Truck
12 2 - Wireline Trucks (USIT/Misc tools)
13 1 - 120 bbl or 80 bbl Vacuum Truck
14 5 - Service Pickup Trucks (various onsite contractors)
15 1 - Delivery Truck (Tractor/Flatbed Trailer)
16 1 - Stinger Truck with flatbed trailer
17

18 *2.12.9.5 Investigate and Remediate Contamination from Abandonment or Drilling of Gas Wells*

19 During the abandonment, work-over, or drilling of gas wells at Playa del Rey, heavy petroleum
20 hydrocarbons (e.g., crude oil) may be present in near-surface soil. This is incidental contamination from
21 normal oil field activities, such as spills of work-over fluid, small oil spills or leaks. Before the wells are
22 drilled and after well abandonment, SoCalGas and its consultants will perform an investigation of
23 potential oil contamination in near-surface soils (down to 15 feet below ground surface). If significant
24 amounts of petroleum are found, SoCalGas and its contractor will remediate or remove the contamination
25 for off-site disposal. Cleanup levels are normally 10,000 ppm, 1,000 ppm, or 100 ppm of Total Petroleum
26 Hydrocarbons, depending on depth to ground water and soil type.
27

28 Each investigation may take up to two (2) weeks to complete; remediation work at each site may continue
29 for up to two (2) months.
30

31 The following equipment will be required to complete remediation activities:

- 32
33 1 - Drilling Rig
34 1 - Backhoe
35 4 - Trucks
36

37 2.13 CONSTRUCTION SEQUENCING

38
39 The Project will be implemented in multiple stages occurring over several years. Figures 5A and 5B show
40 two options for the Interim Phase: Interim Build Out Option A with the gas wells protected in west Area
41 A and Interim Build Out Option B with the gas wells removed. Figure 5C shows the Full Build Out for
42 the Final Phase of the restoration. The Final Phase of the restoration will be implemented using an
43 adaptive management approach. Targeted monitoring of habitat establishment in the Interim Phase will be

1 used to evaluate if and when adaptive management criteria are met for proceeding with the Final Phase of
2 the Project. WRA's CHRAMP includes discussion of the adaptive management plan.

3
4 The likely construction stages are outlined below. Appendix F includes exhibits showing specific
5 construction sequences for a likely construction sequencing scenario. Note that stockpiling of excavated
6 material may be required between stages.

7
8 **Interim Phase:**

9 **1) Stage 1. Area C South Grading and Visitor Center (see Appendix F, Sequences 1-2)**

10 **2) Stage 2. East and South Area B Restoration**

- 11 • Relocate 30-in gas transmission line as needed (Sequence 3)
- 12 • Water control structure(s) (Sequence 4) (may be deferred to Stage 3)
- 13 • Wetland enhancements (e.g., tidal channel excavation, marshplain grading, invasive plant
14 removal) (Sequence 5)

15 **2) Stage 3. Area A Excavation, Start Channel Meanders Excavation, and Levee Construction (two
16 to four construction seasons)**

17 a) Area A wetland restoration

- 18 • Site prep:
 - 19 • Area A gas line removal and well abandonment (Sequence 6): abandon or protect in place
 - 20 gas wells in Area A (Del Rey 13, 14, 15, and 19), and Del Rey 17 in Fiji Way; abandon
 - 21 and/or remove, or protect in place, associated pipelines (see Section 2.10.1)
 - 22 • Construct Ballona Creek pedestrian/bike bridge (Sequence 7)
 - 23 • Construct Lincoln bridge to connect Area A to Area C (Sequence 8)
 - 24 • Clear and grub (Sequence 9)
 - 25 • Area A wetland and tidal channel excavation (Sequence 10), including partial excavation of
 - 26 Ballona Creek meander, and interim water management
 - 27 • Area A perimeter levee construction (Sequence 11)

28 b) Area B wetland restoration

- 29 • Site prep:
 - 30 • Abandon or protect in place gas wells; relocate gas line (see Section 2.10.1) (Sequence
 - 31 12)
 - 32 • Clear and grub North Area B (Sequence 13)
 - 33 • Install temporary water control structure to maintain south Area B drainage during levee
 - 34 construction (Sequence 4)
 - 35 • Area B Levee Construction (estimated two-year duration to manage settlement) (Sequences
 - 36 14 - 15)
 - 37 • Culver Road Levee
 - 38 • West Area B Levee
 - 39 • Partial Excavation of Ballona Creek meander, and interim water management
 - 40 • Stockpile earth to fill Ballona Channel at new downstream meander
 - 41 • Area B managed wetland water control structures (Sequence 22)

42 c) Other Areas and Features

- 1 • Site prep for Area C and B fill placement areas: clear and grub (Sequences 16 and 18)
- 2 • Start Area C fill placement (non-levee material) (Sequence 19)
- 3 • Start Area B fill placement and upland habitat restoration between Culver, Jefferson, and
- 4 Lincoln Blvds (non-levee material) (Sequence 17)
- 5 • West Culver Blvd. stormwater drainage improvement
- 6

7 **3) Stage 3. Ballona Channel Realignment and Levee Removal (one construction season)**

- 8 a) Step 1: Channel Meanders (Sequence 23)
 - 9 • Complete excavation of channel meanders (two) and lower adjacent levee (for stability)
 - 10 • Complete wetland area tidal channel excavation and grading (pannes, seasonal wetlands)
 - 11 • Breach remaining levee sections to connect meanders to existing channel (four locations)
 - 12 • Planting and erosion control Areas A and North Area B
- 13 b) Step 2: Fill Existing Ballona Channel (Sequence 24)
 - 14 • Block Ballona channel at meanders (rock dikes and or cofferdams)
 - 15 • Fill channel between blockages
- 16 c) Step 3: Complete Realignment (Sequence 25)
 - 17 • Levee removal
 - 18 • Armoring
 - 19 • Dredging
 - 20 • Modify water control structures
- 21 d) Step 4: Complete Area C and Area B fill areas (Sequence 20)
 - 22 • Place and compact earth from excavations
 - 23 • Grade seasonal wetlands
 - 24 • Planting and erosion control
- 25 e) Step 5: Public Access features (Sequence 21, 26, 28)
- 26

27 **Final Phase:**

28 **4) Stage 4. West Area A and West Area B Restoration**

- 29 a) West Area B wetland restoration
 - 30 • West Area B channel enhancement (Sequence 27)
 - 31 • Northwest Ballona Creek levee and Interim levee lowering and upland peninsula grading
 - 32 • North Ballona Creek levee breach at existing tide gate (Sequence 29)
- 33 b) Northwest Ballona Creek levee lowering/removal (Sequence 30)
- 34 c) Placement earth from excavations in Area B fill area if needed (Sequences 31 – 32)
- 35
- 36
- 37

1 **3. OPERATIONS AND MAINTENANCE**

2

3 The intent of the Project is to restore a wetland and creek habitat and flood protection system that is

4 sustained by natural processes and requires minimal operations and maintenance (O&M) activities. A

5 new long term O&M Agreement (between LACFCD, CDFG and all project proponents) will need to be

6 established identifying all new operation and maintenance responsibilities that address 1) the newly

7 modified channel and levees 2) water control structures 3) habitat and vegetation and 4) a number of other

8 miscellaneous proposed items. The new long term O&M Agreement will identify those responsible for

9 flood control and non-flood control aspects of the project.

10

11 **3.1 EXISTING LA COUNTY O&M**

12

13 The LA County Flood Control District currently performs maintenance of the existing flood control

14 channel. The USACE (1999) *LA District Operation, Maintenance, Repair, Replacement, and*

15 *Rehabilitation Manual, Los Angeles County Drainage Area, CA* documents O&M responsibilities and

16 procedures. Table 9 lists current LA County maintenance activities (P. Holland, LA County DPW, pers.

17 comm.) and which activities are anticipated to be continued for the Project.

18

19 **Table 9 Existing LA County O&M activities and anticipated continuation of existing O&M.**

Current LA County O&M Activities	Anticipated Continuation of Existing O&M Activities	Note
1. Clean channel invert	No	See Section 4.2
2. Clean trash net	Yes	No change anticipated
3. Inspect and lock gates	Yes	Some new gate locations
4. Inspect and service flap gates	Yes	Existing West Area B SRT flap gates to remain in the Interim Phase; new structures and gates (see Section 4.4 and 2.8)
5. Inspect and service sub-drains	Yes	For existing sub-drains to remain within Project area
6. Maintenance and repair of fence and gates	Yes	Some new fence and gate locations
7. Maintenance and repair of weep holes	Yes	For existing levees and weep holes to remain
8. Midge control	TBD	
9. Operation and maintenance of tidal gates	Yes	Existing West Area B SRT flap gates to remain in the Interim Phase; new structures and gates (see Section 4.4 and 2.8)
10. Pre-emergent weed control	TBD	
11. Spill response	Yes	
12. Weed removal	TBD	
13. Trash free contract	TBD	

20 TBD = to be determined in coordination with LA County

1 3.2 BALLONA CREEK CHANNEL - MONITORING AND MAINTENANCE

2
3 The restored Ballona Creek channel is intended to have no substantial maintenance requirements. A
4 monitoring and as-needed maintenance program will be developed for the channel. The level of channel
5 erosion and deposition during storm flow events is anticipated to be acceptable for the restoration and
6 flood management. The levee heights will be designed to meet flood criteria with a reduced channel
7 cross-section (see the H&H Report Section 6 for additional discussion). This reduced channel cross-
8 section will define a maintenance limit for the channel. The channel cross-section will be monitored to
9 confirm that the cross-section and flood performance is within the maintenance limit. Any major debris or
10 blockage of the channel that may negatively affect flood protection or restoration performance would
11 need to be removed; however, this is not anticipated.

12
13 In locations where armoring is installed to limit erosion, the scour protection would be inspected and
14 maintained as-needed maintenance; however, maintenance is not anticipated to be needed.

15
16 3.3 PERIMETER LEVEES - MONITORING AND MAINTENANCE

17
18 The levees themselves are intended to have no substantial maintenance requirements. The expected
19 maintenance along the levees will be the periodic repaving of the bike path and walking trail, replacement
20 or repair of fencing that may be installed, replacement or repair of any overlook or educational equipment
21 placed along the walking trail, and trash collection and graffiti removal is encouraged for public
22 involvement and habitat care. It is possible that minor erosion measures may be needed periodically.

23
24 3.4 WATER CONTROL STRUCTURES

25 Flap gates will need regular inspection and maintenance to ensure proper operation. Inspection of other
26 structures will also periodically occur, but problems are unlikely except in the very long term. Gates may
27 be adjusted seasonally for habitat management (see Section 2.8)

28
29 3.5 HABITAT AND VEGETATION – MONITORING AND MAINTENANCE

30
31 Portions of the restored site will be planted (e.g., upland, transition zone, high marsh, and low marsh),
32 while other marsh areas may rely on natural recruitment of salt marsh vegetation (e.g., mid marsh).
33 WRA’s CHRAMP includes a revegetation plan, including monitoring and maintenance. Vegetation
34 maintenance, irrigation, and weeding may be required for certain habitats (e.g., for transition and upland
35 habitat plantings).

36
37 Trash removal may also occur for some trash from that is not caught at the existing trash net/boom
38 between Lincoln Blvd. and Culver Blvd. upstream of the restored wetlands and enters restored habitats at
39 accessible locations.

4. LIST OF ACRONYMS

bgs	below ground surface
CHRAMP	Comprehensive Habitat Restoration and Adaptive Management Plan
FWM	Freshwater Marsh
H&H Report	Preliminary Flood Hydrology and Hydraulics Report
MHHW	Mean Higher High Water
MHW	Mean High Water
MLLW	Mean Lower Low Water
MTL	Mean Tide Level
NAVD	North American Vertical Datum of 1988
NGVD	National Geodetic Vertical Datum of 1929
O&M	Operations and Maintenance
PDR	Preliminary Design Report
PID	Photoionization Detector
RS	River Stationing
SAP	Sampling and Analysis Work Plan

5. REFERENCES

- NRC. (2012). *Sea-Level Rise for the Coasts of California, Oregon, and Washington: Past, Present, and Future*. The National Academies Press. Washington, D.C.
- ESA PWA, 2012a: *Ballona Wetlands Restoration Hydrology & Engineering Design Analysis and Permitting Support Work Plan*, May, 2012.
- ESA PWA, 2012b. *Proposed Restoration Hydrology and Engineering Information for EIR/EIS Notice of Preparation/Notice of Intent and USACE Section 408 Permit Application Project Descript, Ballona Wetlands Restoration (D120367), Prepared for the Ballona Wetlands Restoration Project Management Team*, May, 2012.
- ESA PWA, 2013: *Ballona Wetlands Restoration Project Preliminary Hydrology and Hydraulics Report, Draft*, May 8, 2013.
- IACW, 1982. *Bulletin 17-B: U.S. Interagency Advisory Committee on Water Data, 1982, Guidelines for determining flood flow frequency, Bulletin 17-B of the Hydrology Subcommittee: Reston, Virginia, U.S. Geological Survey, Office of Water Data Coordination, [183 p.]. [Available from National Technical Information Service, Springfield VA 22161 as report no. PB 86 157 278 or from FEMA on the World-Wide Web at http://www.fema.gov/mit/tsd/dl_flow.htm]*
- USACE, 1999. *Operation, Maintenance, Repair, Replacement, and Rehabilitation Manual*. Los Angeles County Drainage Area, California. Los Angeles District, Corps of Engineers, Los Angeles CA.
- PSOMAS, 1999. *Playa Vista, Phase II Wetlands Modeling Technical Appendix*. Prepared for Playa Capital Company. December 28, 1999.
- PWA, 2008. *Basis of Restoration Design for Seasonal and Tidal Wetlands - Hamilton Wetland Restoration Project*, Novato, CA. USACE, December 2008.
- PWA and others, 2008: *Ballona Wetland Feasibility Report*, Prepared for the State Coastal Conservancy, Sept, 2008.
- USACE, 2010a. *Ballona Creek Ecosystem Restoration Feasibility Study. Hydraulic Appendix (Present Conditions/Without Project)*
- USACE, 2010b. *Ballona Creek Ecosystem Restoration Feasibility Study. Hydrology Appendix (Present Conditions/Without Project)*
- USACE, 2011. *Sea-Level Change Considerations in Civil Works Programs*. US Army Corps of Engineers, EC 1165-2-212. October 1, 2011.

6. LIST OF PREPARERS

This report was prepared by the following ESA PWA staff:

Mark Lindley, P.E.
Bob Battalio, P.E.
Nick Garrity, P.E.
Scott Stoller, P.E.
Lindsey Sheehan, P.E.
Pablo Quiroga

Input was provided by the following PSOMAS staff:

Mike Crehan, P.E.